

LETTERS & SYMBOLS PLACEMENT SCHEDULE						
STATION	LOCATION	RT OR LT ARROW	"ONLY"	OTHER	TEMPORARY PAVEMENT MARKING -LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III -LETTERS AND SYMBOLS
STAGE 1A						
21+740	WB-RT	1	1		3.4	
21+820	WB-RT	1	1		3.4	
STAGE TOTAL					6.8	0.0
STAGE 1B						
7+335	WB-LT	1	1		3.4	
7+460	EB-LT	1	1		3.4	
7+460	EB-RT	1	1		3.4	
7+460	WB-LT	1	1		3.4	
7+460	WL-RT	1	1		3.4	
7+460	NB-LT	1	1		3.4	
7+460	SB-RT	1	1		3.4	
7+683	EB-LT	1	1		3.4	
7+683	WB-LT	1	1		3.4	
7+683	WB-RT	1	1		3.4	
7+683	NB-LT	1	1		3.4	
7+683	SB-LT	1	1		3.4	
7+850 - 8+040	TWLTL	6	0		9.0	
8+129	EB-LT	1	1		3.4	
8+129	WB-LT	1	1		3.4	
8+129	NB-RT	1	1		3.4	
20+910	NB-LT	1	1		3.4	
21+963	EB-LT	1	1		3.4	
STAGE TOTAL					70.2	0.0
STAGE 2A						
7+335	NB-LT	1	1		3.4	
7+335	WB-LT	1	1		3.4	
7+460	EB-LT	1	1		3.4	
7+460	WB-LT	1	1		3.4	
7+683	EB-LT	1	1		3.4	
7+683	WB-LT	1	1		3.4	
8+129	EB-LT	1	1		3.4	
8+129	WB-LT	1	1		3.4	
8+129	NB-RT	1	1		3.4	
71+125	THRU			RXR	1.2	
STAGE TOTAL					31.8	0.0

LETTERS & SYMBOLS PLACEMENT SCHEDULE (CON'T)						
STATION	LOCATION	RT OR LT ARROW	"ONLY"	OTHER	TEMPORARY PAVEMENT MARKING -LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III -LETTERS AND SYMBOLS
STAGE 2B						
7+683	EB-LT	1	1		3.4	
7+683	WB-LT	1	1		3.4	
10+028	EB-LT	1	1		3.4	
10+028	EB-RT	1	1		3.4	
10+028	WB-LT	1	1		3.4	
10+028	WB-RT	1	1		3.4	
10+028	NB-RT	1	1		3.4	
10+028	SB-RT	1	1		3.4	
STAGE TOTAL					27.2	0.0
STAGE 3A						
7+683	EB-LT	1	1		3.4	
7+683	WB-LT	1	1		3.4	
21+963	EB-LT	1	1			3.4
10+028	EB-LT	1	1		3.4	
10+028	WB-LT	1	1		3.4	
71+125	THRU			RXR	1.2	
STAGE TOTAL					14.8	3.4
STAGE 3B						
7+335	NB-LT	1	1		3.4	
7+335	WB-LT	1	1		3.4	
7+460	EB-LT	1	1		3.4	
7+460	WB-LT	1	1		3.4	
7+683	EB-LT	1	1			3.4
7+683	WB-LT	1	1			3.4
8+129	NB-RT	1	1		3.4	
STAGE TOTAL					17.0	6.8
STAGE 4A						
7+335	WB-LT	1	1			3.4
7+460	EB-LT	1	1			3.4
7+460	WB-LT	1	1			3.4
7+460	SB-LT	1	1			3.4
7+683	EB-LT	1	1			3.4
7+683	WB-LT	1	1			3.4
7+683	NB-LT	1	1			3.4
7+683	SB-LT	1	1			3.4
8+129	EB-LT	1	1			3.4
8+129	WB-LT	1	1			3.4
STAGE TOTAL					0.0	34.0
STAGE 4A						
7+683	SB-RT	1	1			3.4
21+963	EB-LT	1	1			3.4
STAGE TOTAL					0.0	6.8

LETTERS & SYMBOLS PLACEMENT SCHEDULE (CON'T)						
STATION	LOCATION	RT OR LT ARROW	"ONLY"	OTHER	TEMPORARY PAVEMENT MARKING -LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III -LETTERS AND SYMBOLS
STAGE 5A						
7+460	NB-LT	1	1			3.4
7+683	EB-LT	1	1			3.4
7+683	EB-RT	1	1			3.4
7+683	WB-LT	1	1			3.4
7+683	WB-RT	1	1			3.4
7+683	NB-LT	2	2			6.8
7+683	NB-RT	1	1			3.4
7+683	SB-LT	2	2			6.8
7+683	SB-RT	1	1			3.4
8+129	EB-LT	1	1			3.4
8+129	WB-LT	1	1			3.4
8+129	NB-LT	1	1			3.4
8+622	EB-LT	1	1			3.4
9+290	EB-LT	1	1			3.4
9+290	WB-LT	1	1			3.4
10+028	EB-LT	1	1			3.4
10+028	WB-LT	1	1			3.4
STAGE TOTAL					0.0	64.6
STAGE 5B						
10+028	NB-RT	1	1			3.4
9+290	NB-RT	1	1			3.4
STAGE TOTAL					0.0	6.8
STAGE 6						
8+622	SB-RT	1	1			3.4
8+622	SB-LT	1	1			3.4
90+140	THRU			RXR		1.2
STAGE TOTAL					0.0	8.0
PROJECT TOTAL					167.7	130.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 22
FROM US RTE 12 TO BUESCHING RD
MAINTENANCE OF TRAFFIC
SCHEDULE OF QUANTITIES
DRAWN BY MBF
CHECKED BY SMK
DATE 7/21/04