

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2002-022 K	WILL	172	67
STA. 10+00		TO STA. 22+96.05		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62389				

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY
80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	37
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	970
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., RIGID GALVANIZED STEEL PVC COATED	FOOT	985
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., RIGID GALVANIZED STEEL PVC COATED	FOOT	12
81200250	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	1455
81300100	JUNCTION BOX STAINLESS STEEL, ATTACHED TO STRUCTURE, 4"X4"X3"	EACH	16
81300320	JUNCTION BOX STAINLESS STEEL, ATTACHED TO STRUCTURE, 8"X8"X6"	EACH	8
81301200	JUNCTION BOX STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12"X10"X6"	EACH	3
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6200
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 1/C NO. 10	FOOT	3300
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	18
82107110	UNDERPASS LUMINAIRE, 70WATT, HIGH PRESSURE SODIUM	EACH	16
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15' MAST ARM	EACH	15
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	252
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	10
84200700	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	21
X0322696	MAST ARM STEEL, STREET LIGHTING, 15FT	EACH	1
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	3
X8160380	UNIT DUCT, WITH 3-1/C #2 AND 1/C #4 GROUND, 600V (EPR-TYPE RHW) 1 1/4" DIA., POLYETHYLENE	FOOT	8300
X8210055	FLUORESCENT LUMINAIRE FOR SIGN STRUCTURE WITH 2 72" T8 HO LAMP	EACH	10
X8210302	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LUMINAIRES	LSUM	1
X8410102	TEMPORARY LIGHTING SYSTEM	LSUM	1
X8440116	RELOCATE EXISTING LIGHTING UNIT	EACH	21
	REPLACE EXISTING DECAL WITH NEW LUMINAIRE NUMBERING DECAL	EACH	36

PLAN	DATE
BY	
REVIEWED	
ALIGNED	
CHECKED	
RT. OF WAY CHECKED	
NO. _____	
FILE NAME	

PROFILE	DATE
BY	
REVIEWED	
CHECKED	
REMARKS	
STRUCTURE NOTATIONS	
NO. _____	

LTC-02

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE: NONE</p> <p>DATE: 1/4/2005</p> <p>DRAWN BY: SM</p> <p>CHECKED BY: SM</p>

K&E KAM ENGINEERING, INC.
CONSULTING ENGINEERS
707A Davis Road, Suite 205
Elgin, Illinois 60123-1369

1-6-05 OCTOBER, 2004