

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	27 BR	WILL	29	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62424

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES X020-2A		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25					
20200100	EARTH EXCAVATION	CU YD	695	695					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	5	5					
20400800	FURNISHED EXCAVATION	CU YD	90	90					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	15		15				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1090	1090					
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25	25					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	25					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	25					
25100630	EROSION CONTROL BLANKET	SQ YD	1090	1090					
25200200	SUPPLEMENTAL WATERING	UNIT	15	15					
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.25	0.25					
28000400	PERIMETER EROSION BARRIER	FOOT	380	380					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.25	0.25					
40600300	AGGREGATE (PRIME COAT)	TON	1.5	1.5					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	0.1	0.1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ YD	25	25					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	245	245					
42001300	PROTECTIVE COAT	SQ YD	425	425					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	50	50					
44000100	PAVEMENT REMOVAL	SQ YD	155	155					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1085	1085					
44000700	APPROACH SLAB REMOVAL	SQ YD	155	155					
44004250	PAVED SHOULDER REMOVAL	SQ YD	90	90					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	15	15					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	540	540					
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1				
50102400	CONCRETE REMOVAL	CU YD	6.4		6.4				

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES X020-2A		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							
50200100	STRUCTURE EXCAVATION	CU YD	11.2		11.2				
50300225	CONCRETE STRUCTURES	CU YD	6.2		6.2				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	39		39				
50300260	BRIDGE DECK GROOVING	SQ YD	83		83				
50300300	PROTECTIVE COAT	SQ YD	108		108				
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	16		16				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9900		9900				
51500100	NAME PLATES	EACH	1		1				
54215547	METAL END SECTIONS 12"	EACH	2		2				
59000100	EPOXY CRACK SEALING	FOOT	47		47				
60100945	PIPE DRAINS 12"	FOOT	64		64				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	820		820				
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2		2				
60900515	CONCRETE THRUST BLOCKS	EACH	2		2				
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	150		150				
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4				
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4				
66400105	CHAIN LINK FENCE, 4'	FOOT	670		670				
66410300	CHAIN LINK FENCE REMOVAL	FOOT	670		670				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4				
67100100	MOBILIZATION	L SUM	1		1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	150		150				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2130		2038	92			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	33		33				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	900		808	92			
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	150		150				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI-55 (EAST FRONTAGE ROAD)
 OVER SUNNYLAND DRAIN
 SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 12/20/2004

07:02:54 12/20/2004

12/20/2004 11:30:00 AM