

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	27 BR	WILL	29	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62424

SUMMARY OF QUANTITIES			80% FED. 20% FED. TOTAL QUANTITIES X020-2A	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT						
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	150		150			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	350	350				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	195		195			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2			
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	8	8				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6				
70104500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52				
X0712400	TEMPORARY PAVEMENT	SQ YD	455	455				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	45	45				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	20	20				
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	400	400				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1			
Z0002600	BAR SPLICERS	EACH	58		58			
⊙ Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14		14			
⊙ Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14		14			
Z0073700	TEMPORARY WALL BRACING SYSTEM	L SUM	1		1			

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							

⊙ SPTY-3N
• SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI-55 (EAST FRONTAGE ROAD)
OVER SUNNYLAND DRAIN
SUMMARY OF QUANTITIES

PLOT DATE: 12/20/2004

12/20/2004 14:41:31 16/40/4000