

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	QUANTITIES			
			90-FED. 101-STATE URBAN	CIVIL	LIGHTING	SURVEILLANCE
			J000	Y030-1E	Y032-1F	
83600200	LIGHT POLE FOUNDATION, 24" DIA.	FOOT	361	0	361	0
83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	1955	0	1955	0
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	24	0	24	0
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	651	0	651	0
84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	24	0	24	0
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	8	0	8	0
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	8	0	8	0
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	8	0	8	0
86300400	CONTROLLER CABINET TYPE IV	EACH	2	0	0	2
87000212	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2 AND NO. 6 GROUND	FOOT	2300	0	0	2300
<del>87300405</del>	<del>ELECTRIC CABLE AERIAL SUSPENDED, COMMUNICATIONS, NO. 10 3 PAIR</del>	<del>FOOT</del>	<del>800</del>	<del>0</del>	<del>0</del>	<del>800</del>
87502100	TRAFFIC SIGNAL POST, PAINTED STEEL 2.5 FT	EACH	7	0	0	7
87502207	TRAFFIC SIGNAL POST, PAINTED STEEL 5 FT.	EACH	20	0	0	20
87502210	TRAFFIC SIGNAL POST, PAINTED STEEL 7 FT	EACH	9	0	0	9
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	0	0	12
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	9	0	0	9
87900200	DRILL EXISTING HANDHOLE	EACH	18	0	0	18
88600300	DETECTOR LOOP, TYPE III	FOOT	1809	0	0	1809
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3886	0	0	3886
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	3,605	0	0	3,605
X0321973	MODIFY EXISTING SERVICE INSTALLATION	EACH	2	0	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1048	1048	0	0
X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	147,009	0	0	147,009
X0323360	WOODEN POLE REMOVAL	EACH	297	0	289	8
X0323363	ELECTRIC CABLE IN CONDUIT, NO. 12 3/C	FOOT	5134	0	0	5134
X0323364	ELECTRIC CABLE IN CONDUIT NO. 19 6/C	FOOT	2926	0	0	2926
X0324790	ELECTRIC CABLE IN CONDUIT, NO. 19 12/C	FOOT	182	0	0	182
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE, INLET FILTER CLEANING	EACH	282	282	0	0
X0323574	MAINTAIN LIGHTING SYSTEM	CAL MO	33	0	33	0
X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	2,158	0	2,158	0
X0323900	CONCRETE FOUNDATION, TYPE 1	FOOT	206	0	0	206
X0323907	COMMUNICATIONS VAULT	EACH	28	0	0	28
X0323914	FIBER OPTIC CABLE SPLICE - LATERAL	EACH	53	0	0	53
X0323917	CABINET, MODEL 334	EACH	49	0	0	49



Rev. 2-22-05  
 Rev. 1-31-05  
 Rev. 12-29-04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CJM  
 DATE: October 29, 2004 CHECKED BY: JPC

12/07/2004 03:20:05 PM