

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	90% FED.	QUANTITIES		
			10% STATE	CIVIL	LIGHTING	SURVEILLANCE
			URBAN	J000	Y030-1E	Y032-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	797	797	0	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	207	207	0	0
20101000	TEMPORARY FENCE	FOOT	15,366	15,366	0	0
20101700	SUPPLEMENTAL WATERING	UNIT	500	500	0	0
20200100	EARTH EXCAVATION	CY	4,075	3,495	580	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CY	921	700	221	0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	87,017	81,457	5,560	0
25000210	SEEDING, CLASS 2A	ACRE	18.0	16.8	1.2	0.0
25000400	NITROGEN FERTILIZER NUTRIENT	LBS	1,623	1,513	110	0
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LBS	1,623	1,513	110	0
25000600	POTASSIUM FERTILIZER NUTRIENT	LBS	1,623	1,513	110	0
25100630	EROSION CONTROL BLANKET	SO YD	86,933	81,373	5,560	0
25200110	SODDING SALT TOLERANT	SO YD	84	84	0	0
28000250	TEMPORARY EROSION CONTROL SEEDING	LBS	1,675	1,675	0	0
28000400	PERIMETER EROSION BARRIER	FOOT	13,058	9,058	4,000	0
28000510	INLET FILTERS	EACH	141	141	0	0
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SO YD	300	300	0	0
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SO YD	215	215	0	0
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SO YD	83	83	0	0
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SO YD	201	201	0	0
40600200	BITUMINOUS MATERIAL (PRIME COAT)	TON	0.1	0.1	0	0
40600300	AGGREGATE (PRIME COAT)	TON	0.5	0.5	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	132.0	132.0	0	0
44000006	BITUMINOUS SURFACE REMOVAL 1-1/2"	SO YD	241	241	0	0
44000035	BITUMINOUS SURFACE REMOVAL	SO YD	39	39	0	0
44000100	PAVEMENT REMOVAL	SO YD	279	279	0	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	156	156	0	0
44000600	SIDEWALK REMOVAL	SO FT	228	228	0	0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	24	24	0	0
44001980	CONCRETE BARRIER REMOVAL	FOOT	233	233	0	0
44004250	PAVED SHOULDER REMOVAL	SO YD	25	25	0	0
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SO YD	450	450	0	0
50200100	STRUCTURE EXCAVATION	CY	33	33	0	0

1 OF 8



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: CUM  
DATE: October 29, 2004 CHECKED BY: JPC

12/07/2004 08:45:30 AM