


62583

SUMMARY OF QUANTITIES		QUANTITIES				
CODE NO.	ITEM	UNIT	90% FED. 10% STATE	CIVIL	LIGHTING	SURVEILLANCE
			URBAN	J000	Y030-1E	Y032-1F
8100800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	11,673	0	782	10,891
8100100	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	1794	0	1757	37
X8100060	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL, PVC COATED	FOOT	20	0	20	0
X8101300	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL, PVC COATED	FOOT	550	0	550	0
81016400	CONDUIT IN TRENCH, 1 1/4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	517,755	0	0	517,755
81016800	CONDUIT IN TRENCH, 3" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	600	0	600	0
81017000	CONDUIT IN TRENCH, 4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	80	0	0	80
81018525	CONDUIT PUSHED, 2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	1,798	0	0	1,798
81018925	CONDUIT PUSHED, 4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	600	0	0	600
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	11,467	0	0	11,467
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	1,655	0	76	1,579
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1739	0	1739	0
81022300	CONDUIT ENCASED IN CONCRETE, 4" DIA., PVC	FOOT	2,740	0	0	2,740
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	316	0	316	0
<del>81300410</del>	<del>JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 4"</del>	<del>EACH</del>	<del>18</del>	<del>0</del>	<del>0</del>	<del>18</del>
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	272	0	272	0
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	10	0	10	0
81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	20	0	1	19
81300840	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 12"	EACH	2	0	0	2
81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 42" X 36" X 12"	EACH	8	0	8	0
81306400	RELOCATE EXISTING JUNCTION BOX	EACH	64	0	64	0
81306500	REMOVE EXISTING JUNCTION BOX	EACH	11	0	11	0
81400100	HANDHOLE	EACH	1	0	1	0
81400200	HEAVY-DUTY HANDHOLE	EACH	123	0	0	123
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	222,647	0	83,180	139,467
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	62,629	0	62,629	0
81800100	AERIAL CABLE, 3-1/C NO. 3/0, ALUMINUM, WITH MESSENGER WIRE	FOOT	1,400	0	1,400	0
81800700	AERIAL CABLE, 3-1/C NO. 2 AWG, ALUMINUM, WITH MESSENGER WIRE	FOOT	63,601	0	63,601	0
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	42	0	42	0
82106100	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT (INSTALL ONLY)	EACH	824	0	824	0
82107110	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	382	0	382	0
82107310	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	8	0	8	0
83050860	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-6 FT. MAST ARMS	EACH	2	0	2	0



Rev. 1-31-05  
 Rev. 12-29-04  
 Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 31st STREET TO I-57  
 SUMMARY OF QUANTITIES  
 SCALE: NONE  
 DATE: October 29, 2004  
 DRAWN BY: CJM  
 CHECKED BY: JPC

12/07/2004 08:50:45 AM