


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2003-0311	COOK	976	7
STA.	TO STA.			
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

62583

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	QUANTITIES			
			90/FED. 101/STATE URBAN	CIVIL	LIGHTING	SURVEILLANCE
			J000	Y030-1E	Y032 -IF	
X0323957	FIBER OPTIC CABLE SPLICE - MAINLINE	EACH	15	0	0	15
X0324190	REMOVE AND SALVAGE EXISTING SURVEILLANCE EQUIPMENT	LSUM	1	0	0	1
X0324191	REMOVE EXISTING SURVEILLANCE EQUIPMENT	LSUM	1	0	0	1
X0324292	EXISTING MAINTENANCE OF TRAFFIC SURVEILLANCE	CAL MO	36	0	0	36
X0324294	NON-INVASIVE, MAGNETO-INDUCTIVE VEHICLE DETECTOR	EACH	123	0	0	123
X0324433	LIGHT TOWER SERVICE PAD, 6"	SO FT	7,946	7,946	0	0
X0324791	UTILITY TRANSFORMER PAD, 4"	EACH	5	0	5	0
X0324510	LIGHTING CONTROLLER FOUNDATION	EACH	8	0	8	0
X0324591	NON-INVASIVE, MAGNETO-INDUCTIVE VEHICLE DETECTOR ASSEMBLY	EACH	616	0	0	616
X0324592	2070 CONTROLLER	EACH	45	0	0	45
X0324593	HAR FLASHING BEACON ASSEMBLY	EACH	3	0	0	3
X0324594	HIGHWAY ADVISORY RADIO STATION	EACH	1	0	0	1
X0324596	CABINET, MODEL 334 EQUIPMENT, RAMP METER/SYSTEM DETECTOR	EACH	15	0	0	15
X0324597	CLOSED CIRCUIT TELEVISION CABINET	EACH	26	0	0	26
X0324598	RAMP METER FLASHER	EACH	14	0	0	14
X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	98,748	0	450	98,298
<del>X0324600</del>	<del>UPGRADE EXISTING HIGHWAY ADVISORY RADIO STATION</del>	<del>EACH</del>	<del>1</del>	<del>0</del>	<del>0</del>	<del>1</del>
X0324602	UNIT DUCT, WITH 1 RG-8/U COAXIAL CABLE, 1 1/4" DIA., POLYETHYLENE	FOOT	80	0	0	80
X0324606	TEMPORARY CCTV CAMERA STATION, RELOCATE	EACH	6	0	0	6
X0324607	TEMPORARY CCTV CAMERA STATION, REMOVE AND SALVAGE	EACH	10	0	0	10
X0324684	TEMPORARY CCTV CAMERA STATION MONTHLY MAINTENANCE	CAL MO	24	0	0	24
X4066414	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "C", N50	TON	23	4	0	19
X4066426	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX "D", N70	TON	21	21	0	0
X4066614	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0, N50	TON	53	9	0	44
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.33	0.34	0.33
X7015050	PORTABLE CHANGEABLE MESSAGE SIGN	CAL MO	198	0	198	0
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	1,120	1,120	0	0
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	5	5	0	0
X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	73	0	73	0
X8100045	CONDUIT ENCASED, CONCRETE, 3" DIA., PVC	FOOT	126	0	0	126
X8100045	CONDUIT ENCASED, REINFORCED CONCRETE, 1-3" DIA., CNC	FOOT	252	0	252	0



Rev. 1-31-05  
 Rev. 1-13-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
 31st STREET TO I-57

SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: October 29, 2004

DRAWN BY: CJM  
 CHECKED BY: JPC

12/07/2004 10:22:50 AM  
 M:\40468\4681\REV\5-CAT\20\SHP\Contract 2130020052.dwg