

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
866	1181	LAKE	17	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO.: 62606				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE:							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES							
				1000						
				SHANCK AVE.						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	15	15						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	313	313						
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	27	27						
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	2593	2593						
44000110	BITUMINOUS REMOVAL OVER PATCHES 2 1/2"	SQ YD	192	192						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	76	76						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	20	20						
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	97	97						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	21	21						
67100100	MOBILIZATION	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	36	36						
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2612	2612						
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	71	71						
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	36	36						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	34	34						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16						
88600600	DETECTOR LOOP REPLACEMENT	FOOT	220	220						
K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1	1						
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	96						
X4200740	PORTLAND CEMENT CONCRETE OVERLAY, 4"	SQ YD	2593	2593						
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1						

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	

PLOT DATE: 12/30/2004

12/30/2004  
c:\pcc\sect\hml\2003\hml\2003\sum.qrt