

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	0104RS-3	COOK	28	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTACT # 62716

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY URBAN 1000 100% STATE	BRIDGE URBAN SFTY-2A 100% STATE			
20800150	TRENCH BACKFILL	CU YD	120	120				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	106	106				
25000210	SEEDING, CLASS 2A	ACRE	0.03	0.03				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1				
25200110	SODDING, SALT TOLERANT	SQ YD	106	106				
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	25	25				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	41	41				
40600300	AGGREGATE (PRIME COAT)	TON	206	206				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	5	5				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	408	408				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	214	214				
42001300	PROTECTIVE COAT	SQ YD	405	405				
44000100	PAVEMENT REMOVAL	SQ YD	69	69				
44000120	BITUMINOUS REMOVAL OVER PATCHES 5"	SQ YD	765	765				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	17	17				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	874	874				
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	5	5				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	171	171				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	402	402				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	243	243				
44900100	REMOVAL AND REPLACEMENT OF PREFORMED ELASTOMERIC COMPRESSION JOINT SEAL	FOOT	146		146			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	15	15				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1320	1320				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	154	154				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	37	37				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	33	33				
55100300	STORM SEWER REMOVAL 8"	FOOT	56	56				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY URBAN 1000 100% STATE	BRIDGE URBAN SFTY-2A 100% STATE			
55100400	STORM SEWER REMOVAL 10"	FOOT	28	28				
55100900	STORM SEWER REMOVAL 18"	FOOT	19	19				
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3				
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4	4				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	26	26				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	14	14				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14				
60404940	FRAMES AND GRATES, TYPE 23	EACH	22	22				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	7	7				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	6	6				
60500050	REMOVING CATCH BASINS	EACH	3	3				
60500060	REMOVING INLETS	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12084	12084				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	254	254				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	34330	34330				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1145	1145				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1360	1360				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	258	258				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
55TH ST.
DUPAGE COUNTY LINE RD. TO BRAINARD AVE.

12/22/2004 11:06:00 AM