



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

March 1, 2005

SUBJECT: FAI Route 90/94
Project IM-094-3(384)057
Section 2004-069RS
Cook County
Contract No. 62808
Item No. 1, March 11, 2005 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 80, 81 & 91 of the Special Provisions.
2. Revised page ii of the Table of Contents.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger DE'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe; Roger Driskell; Jim White; Design & Environment File

TBW:TK:jc

STORM WATER POLLUTION PREVENTION PLAN..... 33
CONTRACTOR CERTIFICATION STATEMENT 46
BITUMINOUS BASE COURSE / WIDENING SUPERPAVE 48
BITUMINOUS EQUIPMENT, SPREADING AND FINISHING MACHINE (BDE)..... 53
COARSE AGGREGATE FOR TRENCH BACKFILL, BACKFILL AND BEDDING (BDE)..... 53
CONCRETE ADMIXTURES (BDE)..... 59
CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE)..... 63
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 70
EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE)..... 76
EXPANSION JOINTS (BDE)..... 77
FLAGGER VESTS (BDE)..... 77
FREEZE-THAW RATING (BDE) 77
FURNISHED EXCAVATION (BDE)..... 78
HAND VIBRATOR (BDE) 79
INLET FILTERS (BDE)..... 79
PARTIAL PAYMENTS (BDE)..... 81
PAVEMENT THICKNESS DETERMINATION FOR PAYMENT (BDE) 82
PAYMENTS TO SUBCONTRACTORS (BDE)..... 88
PERSONAL PROTECTIVE EQUIPMENT (BDE)..... 88
PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)..... 89
PORTLAND CEMENT (BDE)..... 89
PORTLAND CEMENT CONCRETE (BDE)..... 90
PRECAST CONCRETE PRODUCTS (BDE) 90
PREFORMED RECYCLED RUBBER JOINT FILLER (BDE) 91
RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE) 92
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 95
SUBGRADE PREPARATION (BDE)..... 96
SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE) 97
SURFACE TESTING OF PAVEMENTS (BDE)..... 102
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)..... 108
TRUCK BED RELEASE AGENT (BDE)..... 109
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 109
STEEL COST ADJUSTMENT (BDE)..... 110

Revised 03-01-2005

variety of existing and proposed drainage structure frames that are present on this contract. The inlet filter assembly frame shall not cause the drainage structure grate to extend higher than 6 mm (1/4 in.) above the drainage structure frame.

- (2) Grate Lock. When the inlet is located in a traffic lane, a grate lock shall be used to secure the grate to the frame. The grate lock shall conform to the manufacturer's requirements for materials and installation.
- (3) Geotextile Fabric Bag. The sediment bag shall be constructed of an inner filter bag and an outer reinforcement bag.
- a. Inner Filter Bag. The inner filter bag shall be constructed of a polypropylene geotextile fabric with a minimum silt and debris capacity of 0.06 cu m (2.0 cu ft). The bag shall conform to the following requirements:

Inner Filter Bag		
Material Property	Test Method	Minimum Avg. Roll Value
Grab Tensile Strength	ASTM D 4632	45 kg (100 lb)
Grab Tensile Elongation	ASTM D 4632	50%
Puncture Strength	ASTM D 4833	29 kg (65 lb)
Trapezoidal Tear	ASTM D 4533	20 kg (45 lb)
UV Resistance	ASTM D 4355	70% at 500 hours
Actual Open Size	ASTM D 1420	212 µm (No. 70 sieve US)
Permittivity	ASTM D 4491	2.0/sec
Water Flow Rate	ASTM D 4491	5900 Lpm/sq m (145 gpm/sq ft)

- b. Outer Reinforcement Bag. The outer reinforcement bag shall be constructed of polyester mesh material that conforms to the following requirements:

Outer Reinforcement Bag		
Material Property	Test Method	Value
Content	ASTM D 629	Polyester
Weight	ASTM D 3776	155 g/sq m (4.55 oz/sq yd) ±15%
Whales (holes)	ASTM D 3887	7.5 ± 2 holes/25 mm (1 in.)
Chorses (holes)	ASTM D 3887	15.5 ± 2holes/25 mm (1 in.)
Instronball Burst	ASTM D 3887	830 kPa (120 psi) min.
Thickness	ASTM D 1777	1.0 ± 0.1 mm (0.040 ± 0.005 in.)

- (4) Certification. The manufacturer shall furnish a certification with each shipment of inlet filters, stating the amount of product furnished, and that the material complies with these requirements."

Revised 03-01-2005

PARTIAL PAYMENTS (BDE)

Effective: September 1, 2003

Revise Article 109.07 of the Standard Specifications to read:

"109.07 Partial Payments. Partial payments will be made as follows:

- (a) Progress Payments. At least once each month, the Engineer will make a written estimate of the amount of work performed in accordance with the contract, and the value thereof at the contract unit prices. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1000.00 will be approved for payment other than the final payment.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved. Furthermore, progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c).

- (b) Material Allowances. At the discretion of the Department, payment may be made for materials, prior to their use in the work, when satisfactory evidence is presented by the Contractor. Satisfactory evidence includes justification for the allowance (to expedite the work, meet project schedules, regional or national material shortages, etc.), documentation of material and transportation costs, and evidence that such material is properly stored on the project or at a secure location acceptable and accessible to the Department.

Material allowances will be considered only for nonperishable materials when the cost, including transportation, exceeds \$10,000 and such materials are not expected to be utilized within 60 days of the request for the allowance. For contracts valued under \$500,000, the minimum \$10,000 requirement may be met by combining the principal (material) product of no more than two contract items. An exception to this two item limitation may be considered for any contract regardless of value for items in which material (products) are similar except for type and/or size.

Material allowances shall not exceed the value of the contract items in which used and shall not include the cost of installation or related markups. Amounts paid by the Department for material allowances will be deducted from estimates due the Contractor as the material is used. Two-sided copies of the Contractor's cancelled checks for materials and transportation must be furnished to the Department within 60 days of payment of the allowances or the amounts will be reclaimed by the Department."

Revised 03-01-2005

(GGBF) slag shall be governed by the AASHTO or ASTM standard specification referenced in the Standard Specifications.

For all other precast concrete products using Class PC concrete or other mixtures, portland cement replacement with fly ash or GGBF slag shall be approved by the Engineer. Class F fly ash shall not exceed 15 percent by mass (weight) of the total portland cement and Class F fly ash. Class C fly ash shall not exceed 20 percent by mass (weight) of the total portland cement and Class C fly ash. GGBF slag shall not exceed 25 percent by mass (weight) of the total portland cement and GGBF slag.

Concrete mix designs, for precast concrete products, shall not consist of portland cement, fly ash and GGBF slag.

Ready-Mixed Concrete. Delete the last paragraph of Article 1020.11(a) of the Standard Specifications.

Shipping. When a precast concrete product has attained the specified strength, the earliest the product may be loaded, shipped, and used is on the fifth calendar day. The first calendar day shall be the date casting was completed.

Acceptance. Products which have been lot or piece inspected and approved by the Department prior to July 1, 1999, will be accepted for use on this contract.

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)

Effective: November 1, 2002

Revise Article 503.02(c) of the Standard Specifications to read:

“(c) Prefomed Expansion Joint Filler..... 1051”

Revise Article 637.02(d) of the Standard Specifications to read:

“(d) Prefomed Expansion Joint Filler..... 1051”

Add the following Article to Section 1051 of the Standard Specifications:

“1051.10 Prefomed Recycled Rubber Joint Filler. Prefomed recycled rubber joint filler shall consist of ground tire rubber, free of steel and fabric, combined with ground scrap or waste polyethylene. It shall not have a strong hydrocarbon or rancid odor and shall meet the physical property requirements of ASTM D 1752. Water absorption by volume shall not exceed 5.0 percent.”

Revised 03-01-2005