F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-069RS	COOK	61	8
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62808

SUMMARY OF QUANTITIES

URBAN
90% FED./10% STATE

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY J000-2A
20200100	EARTH EXCAVATION	CU YD	145	145
20400800	FURNISHED EXCAVATION	CU YD	17	17
20700220	POROUS GRANULAR EMBANKMENT	CU YD	105	105
20800150	TRENCH BACKFILL	CU YD	63	63
28000510	INLET FILTERS	EACH	17	17
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B, 8"	SQ YD	4,539	4,539
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.01	0.01
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	4,066	4,066
42001300	PROTECTIVE COAT	SQ YD	4,748	4,748
44000100	PAVEMENT REMOVAL	SQ YD	2,854	2,854
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	32	32
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,193	1,193
44000600	SIDEWALK REMOVAL	SQ FT	6,263	6,263
55100300	STORM SEWER REMOVAL 8"	FOOT	73	73
60202505	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 1 FRAME OPEN LID (CITY OF CHICAGO)	EACH	9	9
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7	7
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1
60500050	REMOVING CATCH BASINS	EACH	6	6
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	1,192	1,192
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	3	3
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	38	38
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	34	34
X0324350	COMBINED SEWERS, ESVCP, TYPE 2, 18"	FOOT	25	25
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	61	61
X0712400	TEMPORARY PAVEMENT	SQ YD	9	9
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
X6065740	CONCRETE MEDIAN SURFACE, 5" MODIFIED	SQ FT	1,365	1,365
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	1,190	1,190
XX157200	CITY ELECTRIC MANHOLES TO BE ADJUSTED	EACH	1	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~1 HOUR~~		
X0324166	COMBINED SEWERS, ESVCP, TYPE 2, 15"	FOOT	20	20
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	6	6

~~Q 4080~~
* SPECIALTY ITEMS

• DENOTES SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
53rd ST TO 51st ST (WELLS STREET)

SUMMARY OF QUANTITIES

SCALE: NONE — DRAWN BY: PHP
DATE: December 17, 2004 — CHECKED BY: JAL

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

m:\P40456\CIVIL\4 Cnt\5\Add_Cnt\3011\Staff\General\50998401CA.STF
12/15/2004 3:52:12 PM