

SUMMARY OF QUANTITIES

901.FED.
101.STATE
URBAN
ROADWAY

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-070RS	COOK	60	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
62809				

CODE NO.	ITEM	UNIT	QUANTITY	J000-2A
20200100	EARTH EXCAVATION	CU YD	372	372
20700220	POROUS GRANULAR EMBANKMENT	CU YD	106	106
20800150	TRENCH BACKFILL	CU YD	33	33
28000510	INLET FILTERS	EACH	16	16
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SO YD	4,459	4,459
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	4,058	4,058
42001300	PROTECTIVE COAT	SO YD	4,663	4,663
44000100	PAVEMENT REMOVAL	SO YD	2,657	2,657
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	97	97
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,202	1,202
44000600	SIDEWALK REMOVAL	SO FT	7,227	7,227
Δ 55039700'	STORM SEWERS TO BE CLEANED	FOOT	16	16
55100300	STORM SEWER REMOVAL 8"	FOOT	163	163
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	4	4
60202605	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1
60235200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2
60500050	REMOVING CATCH BASINS	EACH	6	6
60500060	REMOVING INLETS	EACH	7	7
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	888	888
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	98	98
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	38	38
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	32	32
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SO FT	1,262	1,262
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	5	5
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	1,202	1,202
XX157200	CITY ELECTRIC MANHOLES TO BE ADJUSTED	EACH	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0018000	TRAINERS	UNIT		
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	13	13
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	4	4


Δ NON-PARTICIPATING
④-1488

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
53rd ST TO 51st ST (WENTWORTH AVENUE)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: AMM
DATE: DECEMBER 17, 2004 CHECKED BY: JAL



MAP:40468.C:\WIN4_CIT\9468_CIT\9468.ctb General\1009150124.dwg 12/15/2004 10:20:02 PM