

ROADWAY REMOVAL SCHEDULE

STATION TO STATION	SHEET	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL
		SQ YD	SQ YD	FOOT	SO FT
WENTWORTH AVENUE					
171+33.51 TO 173+00.00	1	341		166	1,090
173+00.00 TO 178+00.00	2	1,414	31	500	3,020
178+00.00 TO 183+00.00	3	830	66	500	2,883
183+00.00 TO 183+35.83	4	72		36	234
TOTALS		2,657	97	1,202	7,227

ROADWAY ITEMS SCHEDULE

STATION TO STATION	SHEET	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	PORTLAND CEMENT CONC. PAVEMENT, 10" (JOINTED)	PROTECTIVE COAT	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (MODIFIED)	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	COMBINATION CONCRETE CURB & GUTTER, TYPE B-V.12
		SQ YD	SQ YD	SO YD	FOOT	SO FT	FOOT
WENTWORTH AVENUE							
171+33.51 TO 173+00.00	1	602	555	608	71		166
173+00.00 TO 178+00.00	2	1,855	1,667	1,870	414		500
178+00.00 TO 183+00.00	3	1,858	1,705	2,026	367	1,155	500
183+00.00 TO 183+35.83	4	144	131	159	36	107	36
TOTALS		4,459	4,058	4,663	888	1,262	1,202

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE FACTOR *	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)	POROUS GRANULAR EMBANKMENT
	CU YD	CU YD	CU YD	CU YD	CU YD
WENTWORTH					
STAGE 2	121	103	32	71	106
STAGE 3	251	213	83	130	0
TOTAL	372				106

* THE SHRINKAGE FACTOR USED TO CALCULATE EARTHWORK QUANTITIES IS 15%.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
53rd ST TO 51st ST (WENTWORTH AVENUE)

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: DECEMBER 17, 2004

DRAWN BY: AMM
CHECKED BY: JAL