F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-071RS	COOK	54	8
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62810

m:\pf04169\dn14 ctr9\add_ctr\9h16\sht\general\sg8b012a.sht

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL 10% STATE URBAN ROADWAY J000-2A
20200100	EARTH EXCAVATION	CU YD	155	155
20400800	FURNISHED EXCAVATION	CU YD	5	5
20700220	POROUS GRANULAR EMBANKMENT	CU YD	51	51
20800150	TRENCH BACKFILL	CU YD	48	48
28000510	INLET FILTERS	EACH	10	10
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	3,741	3,741
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	3,392	3,392
42001300	PROTECTIVE COAT	SQ YD	3,913	3,913
44000100	PAVEMENT REMOVAL	SQ YD	2,774	2,774
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	21	21
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	993	993
44000600	SIDEWALK REMOVAL	SQ FT	6,267	6,267
44002000	CONCRETE CURB REMOVAL	FOOT	20	20
55100300	STORM SEWER REMOVAL 8"	FOOT	83	83
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	5	5
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	7	7
60500050	REMOVING CATCH BASINS	EACH	5	5
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	993	993
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
81400115	HANDHOLE TO BE ADJUSTED	EACH	2	2
81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	1	1
X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	17	17
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	30	30
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	20	20
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	65	65
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	754	754
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	989	989
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
~~Z0076600~~	~~TRAINEES~~	~~HOUR~~		
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	5	5
X0324166	COMBINED SEWERS, ESVCP, TYPE 2, 15"	FOOT	25	25

~~OY080~~

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
51st ST TO 48th PL (WELLS STREET)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: December 17, 2004
DRAWN BY: NJH
CHECKED BY: PHP

12/9/2004 9:06:18 AM