F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-073RS	COOK	74	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62812

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	URBAN ROADWAY 90% FEDERAL 10% STATE J000-2A
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,958	1,958
* 81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	2	2
X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	105	105
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	273	273
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	42	42
X0324166	COMBINED SEWERS, ESVCP, TYPE 2, 15"	FOOT	25	25
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	25	25
X0324872	CAST IN PLACE TACTILE/DETECTABLE WSS RAMPS FOR PEOPLE W/DISABILITIES	SQ FT	24	24
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	3	3
X4023000	TEMPORARY ACCESS (ROAD)	EACH	2	2
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	4,007	4,007
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	11	11
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	1,202	1,202
XX157200	CITY ELECTRIC MANHOLES TO BE ADJUSTED	EACH	12	12
Z0002600	BAR SPLICERS	EACH	138	138 △1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
⊙ ~~[illegible]~~	~~TRAINEES~~	~~HOUR~~		
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	18	18

⊙ Y080

△1 Rev. 2-22-05
Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
51st ST (WENTWORTH AVE AND WELLS ST)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: LC
DATE: December 23, 2004 CHECKED BY: JAL

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

m:\p40468\civil\4 cntr9\add_cntr\9bl8\sht\general\sq9bl8022a.sht
12/21/2004 3:15:29 PM