

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				ROADWAY		SAFETY	BRIDGES	
				PCC PAVEMENT J000-2A			WILLOW RD. OVER MILWAUKEE AVE. X271-2A	WILLOW RD. OVER DES PLAINES RIVER X071-2A
△ 80800100	TEMPORARY WOOD POLE, 30 FT., CLASS 4	EACH	16			J000-2A	16	
△ 81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	735				735	
△ 81800200	AERIAL CABLE, 2-1/2 NO.4 WITH MESSENGER WIRE	FOOT	3,100				3,100	
△ X8420102	REMOVE EXISTING UNDERPASS LUMINAIRE, AND SALVAGE	EACH	12				12	
△ <del>81102600</del>	<del>CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC</del>	FOOT	80				80	
△ 82107110	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	12				12	
△ X8080150	TEMPORARY WOOD POLE, 15 FT., CLASS 4	EACH	13				13	
△ X8150330	JUNCTION BOX, TYPE-A 16" X 14" X 6"	EACH	2				2	
△ X8150330	JUNCTION BOX, TYPE-B 12" X 10" X 6"	EACH	6				6	
△ X8150340	JUNCTION BOX, TYPE-C 6" X 6" X 6"	EACH	12				12	
△ X0324907	TEMPORARY MAST ARM 15 FT.	EACH	13				13	
△ X0324908	TEMPORARY LUMINAIRE, ROADWAY LIGHTING, HIGH PRESSURE SODIUM, 250 WATT, 240 VOLT, HORIZONTAL MOUNT, TYPE II, MEDIUM SEMI-CUTOFF	EACH	4				4	
△ X0324909	TEMPORARY LUMINAIRE, ROADWAY LIGHTING, HIGH PRESSURE SODIUM, 100 WATT, 240 VOLT, HORIZONTAL MOUNT, TYPE II, MEDIUM SEMI-CUTOFF	EACH	13				13	
△ X8160365	UNIT DUCT, WITH 3-1/2 NO. 4 AND 1/2 NO. 4 GROUND, 600V (EPR-TYPE RHW), 1/4" DIA., POLYETHYLENE	FOOT	80				80	
△ 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/2 NO. 10	FOOT	1,080				1,080	
△ <del>81100300</del>	<del>CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL</del>	<del>FOOT</del>	<del>360</del>				<del>360</del>	
△ 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	57	57				
△ 81400200	HEAVY DUTY HANDHOLE	EACH	1	1				
△ 87900200	DRILL EXISTING HANDHOLE	EACH	1	1				
△ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	291	291				
△ 89502300	REMOVE EXISTING CABLE FROM CONDUIT	FOOT	80	80				
△ 89502380	REMOVE EXISTING HANDHOLE	EACH	1	1				
△ XX002104	ELECTRIC CABLE IN CONDUIT NO. 14 2/C TWISTED, SHIELDED	FOOT	100	100				
□ Z0076600	TRAINNEES	HOURS	2,000	2,000				

△ DENOTES SPECIALTY ITEM □ Y080

S00-6

<b>Edwards AND Kelcey</b>	
REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 WILLOW ROAD  
 OVER US 45/IL 21 (MILWAUKEE AVE)  
 AND OVER DES PLAINES RIVER

SCALE: \_\_\_\_\_ DRAWN BY: TCG  
 DATE: JANUARY 2005 CHECKED BY: DES

P:\00001914\0000\Advance Contract\INALS00-rew\sec071