

EARTH WORK SCHEDULE

STAGE 2

STATION TO STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUST FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL FOR LANDSCAPE (CU YD)
WILLOW ROAD							
384+90 390+56.91	401	342	1,733	-1,391	443	240	203
392+99.21 396+39.01	99	84	1,426	-1,342	320	165	155
399+41.61 402+80	433	368	132	236	110	136	30
TOTAL STAGE 2	933	794	3,291	-2,497	873	485	388

TOPSOIL FOR LANDSCAPE AT 4" = 3,492 SQ. YD.


STAGE 3

STATION TO STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUST FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	TOPSOIL BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	TOPSOIL FOR LANDSCAPE (CU YD)
WILLOW ROAD							
382+90 390+56.91	381	324	1,521	-1,197	351	209	142
392+99.21 396+39.01	20	17	2,136	-2,119	291	150	141
399+41.61 402+80	271	231	63	168	81	53	28
TOTAL STAGE 3	672	572	3,720	-3,148	723	412	311

TOPSOIL FOR LANDSCAPE AT 4" = 2,799 SQ. YD.

- NOTES:
- SHRINKAGE FACTOR: 15%
 - DEPTH OF TOPSOIL EXCAVATION IS 6 INCHES.

SCH-2

		ILLINOIS DEPARTMENT OF TRANSPORTATION	
		SCHEDULE OF QUANTITIES	
REVISIONS		WILLOW ROAD OVER US 45/IL 21 (MILWAUKEE AVE) AND OVER DES PLAINES RIVER	
NAME	DATE	SCALE	DRAWN BY CADD
		DATE	CHECKED BY PJM
		JANUARY 2005	

12/28/2004 09:17:07 AM