

62850

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	0913.1 RS-1	COOK	52	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		US 12 TO IL 83 MAINLINE	US 12 TO IL 83 FRONTAGE	IL 83 TO RAILROAD MAINLINE	IL 83 TO RAILROAD FRONTAGE	RAILROAD TO IL 21 MAINLINE	RAILROAD TO IL 21 FRONTAGE
				I000-2A	I000	I000-2A	I000	I000-2A	I000
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2695	2695					
35500600	BITUMINOUS BASE COURSE 9"	SQ YD	60		60				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	117	31	29	13	12	16	16
40600300	AGGREGATE (PRIME COAT)	TON	589	155	150	63	60	81	80
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	30	8	7	4	3	4	4
40600895	CONSTRUCTING TEST STRIP	EACH	3	1		1	1		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	160	135	25				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3524	690	440	320	294	900	880
40600990	TEMPORARY RAMP	SQ YD	990	400	150			220	220
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	785	345	440				
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	200			120		80	
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	35	35					
42001300	PROTECTIVE COAT	SQ YD	9000	2315	3885	712	854	556	678
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	15085	15085					
44000114	BITUMINOUS REMOVAL OVER PATCHES 3 1/2"	SQ YD	3904	1669	2235				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	32636	8700	12290	2750	3435	2500	2961
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	6762	1725	4725	312			
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	500			500			
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	3832	396	3436				
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	13046	1045	11075	926			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	22933	5350	5340	1921	4038	2612	3672
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	3512	1400	1200	184	423	100	205
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	8920	3140	3130	314	667	335	1334
44213200	SAW CUTS	FOOT	6370	6370					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	585		585				
55039700	STORM SEWERS TO BE CLEANED	FOOT	13033	3710	2045			4260	3018
60250300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	98	5	5	33	17	23	15
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	321	86	146	7	44	8	30
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	3	2				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		US 12 TO IL 83 MAINLINE	US 12 TO IL 83 FRONTAGE	IL 83 TO RAILROAD MAINLINE	IL 83 TO RAILROAD FRONTAGE	RAILROAD TO IL 21 MAINLINE	RAILROAD TO IL 21 FRONTAGE	
				I000-2A	I000	I000-2A	I000	I000-2A	I000	
60254330	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	6					3	2	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3					2	1	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	38	2	1	19	16			
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	18	4	7		4	3		
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	77	34	13		20	10		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	6762	1725	4725	312				
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	4362	396	3436	530				
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	225		225					
63100005	TRAFFIC BARRIER TERMINAL, TYPE 4	EACH	3		3					
63200310	GUARDRAIL REMOVAL	FOOT	300		300					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	1.5	1.5	1.5	1.5	1.5	1.5	1.5
67100100	MOBILIZATION	L SUM	1	0.2	0.15	0.2	0.1	0.2	0.15	0.15
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD T01421	L SUM	1	0.2	0.15	0.2	0.1	0.2	0.15	0.15
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD T01422	L SUM	1	0.2	0.15	0.2	0.1	0.2	0.15	0.15
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD T01601	L SUM	1	0.2	0.15	0.2	0.1	0.2	0.15	0.15
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD T01701	L SUM	1	0.2	0.15	0.2	0.1	0.2	0.15	0.15
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD T01801	L SUM	1		0.5		0.5			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	49	22	27					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16692	2713	1230	2877	3015	2931	3926	3926
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	496.6	72.6		74				350
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	118276	43425	3384	28609	2764	36544	3550	3550
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1222	270		452				500
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	460	250	210					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	542	110	72	292				68
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	47221	16085	1892	11665	1927	13159	2493	2493
70400100	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	5742	5742						

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 F.A.P. RTE. 305/ PALATINE RD.
 US 12 (RAND RD.) TO IL 21 (MILWAUKEE AVE.)

PLOT DATE: 12/21/2004

12/21/2004 08:35:44 12/21/2004