

62850

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	0913.1 RS-1	COOK	52	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		US 12 TO IL 83 MAINLINE	US 12 TO IL 83 FRONTAGE	IL 83 TO RAILROAD MAINLINE	IL 83 TO RAILROAD FRONTAGE	RAILROAD TO IL 21 MAINLINE	RAILROAD TO IL 21 FRONTAGE
				I000-2A	I000	I000-2A	I000	I000-2A	I000
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296.6	72.6	74			150	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	118276	43425	3384	28609	2764	36544	3550
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1072	270	452			350	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	460	250	210				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	542	110	72	292		68	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1916	523	353	512	138	200	190
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3		3				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1379	471	318	512		40	38
*81400115	HANDHOLE TO BE ADJUSTED	EACH	21	2	9			10	
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	4955	2230		1608		1117	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	205.6				51.4	
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	210		60		150		
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	2680	2680					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	12204	302	5457		2523		3922
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	13286	6250		3076		3960	
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	9644	2190	1389	1005	791	1521	2748
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	86364	10713	18047	6883	15902	11728	23091
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	530			530			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	8595	3600	4995				
X4421000	PARTIAL DEPTH PATCHING	TON	1958	415	130	391	437	430	155
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	10278	2470	770	2322	2596	1696	424
X6370600	CONCRETE BARRIER REPAIR (SPECIAL)	CU YD	35			20		15	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	47	32	15				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	245	93	152				
Z0030060	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 2	EACH	4	4					

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		US 12 TO IL 83 MAINLINE	US 12 TO IL 83 FRONTAGE	IL 83 TO RAILROAD MAINLINE	IL 83 TO RAILROAD FRONTAGE	RAILROAD TO IL 21 MAINLINE	RAILROAD TO IL 21 FRONTAGE
				I000-2A	I000	I000-2A	I000	I000-2A	I000
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1				

Δ SFTY-3W
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. RTE. 305/ PALATINE RD.
US 12 (RAND RD.) TO IL 21 (MILWAUKEE AVE.)

12/22/2004 10:18:50 AM C:\p18050.mxd