F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0196	37RS-3	LAKE	12	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO.: 62860

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A IVANHOE RD.					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	20	20					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5					
40600300	AGGREGATE (PRIME COAT)	TON	1	1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	108	108					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	39	39					
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	2564	2564					
44000110	BITUMINOUS REMOVAL OVER PATCHES 2 1/2"	SQ YD	280	280					
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	132	132					
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	37	37					
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	111	111					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	27	27					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2458	2458					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	160	160					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: I000-2A IVANHOE RD.					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2276	2276					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	22	22					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	160	160					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2276	2276					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	22	22					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13	13					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	55	55					
	X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	96					
	X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	251	251					
	X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	108	108					

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 12/23/2004

12/23/2004