

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	BTIB,D,E,F,&PJ-7	WILL	16	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

LOCATION OF WORK: INTERSTATE 55 OVER THE DES PLAINES RIVER Structures: 099-0008 & 099-0009				
				URBAN
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE: SFTY - 2A
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	
50102400	CONCRETE REMOVAL	CU YD	28.9	28.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33.7	33.7
50501130	STRUCTURAL STEEL REPAIR	POUND	820	820
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10,800	10,800
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	240	240
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	240	240
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	130	130
X0321744	SILICONE JOINT SEALER 2"	FOOT	36	36
X0322939	SILICONE JOINT SEALER 2 1/2"	FOOT	36	36
X0320887	POLYMER CONCRETE	CU FT	2	2
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	36	36
X0323341	BRIDGE EXPANSION JOINT SYSTEM	FOOT	36	36
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	45	45
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
Z0002600	BAR SPLICERS	EACH	174	174
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	0.5	0.5
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	72	72

Δ SFTY-3N
* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES SCALE: DATE	DRAWN BY CHECKED BY
NAME	DATE		

Rev.