

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1313.1 B	COOK	193	4

CONTRACT NO. 62878

80% FED. / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE								50/50 LOCAL+STATE PARTICIPATION SFTY-1B	
				ROADWAY	ROADWAY	BRIDGE (ELMHURST)	RETAINING WALLS	SIGNAL ELMHURST	SIGNS	LIGHTING			
				J000-2A	I000-2A	X271-2A	Y007	Y031-1F	Y002-1C	Y030-1E			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	44	0	44	0	0	0	0	0	0	0	
20101100	TREE TRUNK PROTECTION	EACH	9	0	9	0	0	0	0	0	0	0	
20200100	EARTH EXCAVATION	CU YD	7574	0	7574	0	0	0	0	0	0	0	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1126	0	1126	0	0	0	0	0	0	0	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4.2	0	0	4.2	0	0	0	0	0	0	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	0	100	0	0	0	0	0	0	0	
20800150	TRENCH BACKFILL	CU YD	4616	0	4616	0	0	0	0	0	0	0	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6751	0	6751	0	0	0	0	0	0	0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	126	0	126	0	0	0	0	0	0	0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	126	0	126	0	0	0	0	0	0	0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	126	0	126	0	0	0	0	0	0	0	
25200110	SODDING, SALT TOLERANT	SQ YD	6751	0	6751	0	0	0	0	0	0	0	
28000510	INLET FILTERS	EACH	68	0	68	0	0	0	0	0	0	0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3	3	0	0	0	0	0	0	0	0	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	10,980	0	10,980	0	0	0	0	0	0	0	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	347	0	347	0	0	0	0	0	0	0	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	27	0	27	0	0	0	0	0	0	0	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	391	0	391	0	0	0	0	0	0	0	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9107	0	6644	0	0	0	0	0	2463	0	
44000100	PAVEMENT REMOVAL	SQ YD	13357	0	13357	0	0	0	0	0	0	0	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	916	0	916	0	0	0	0	0	0	0	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6154	0	6154	0	0	0	0	0	0	0	
44000600	SIDEWALK REMOVAL	SQ FT	4326	0	4326	0	0	0	0	0	0	0	
44000700	APPROACH SLAB REMOVAL	SQ YD	1003	1003	0	0	0	0	0	0	0	0	
44003100	MEDIAN REMOVAL	SQ FT	9461	0	9461	0	0	0	0	0	0	0	
44003500	MEDIAN REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	2521	0	2521	0	0	0	0	0	0	0	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	72	72	0	0	0	0	0	0	0	0	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	16	16	0	0	0	0	0	0	0	0	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	126	126	0	0	0	0	0	0	0	0	
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	185	185	0	0	0	0	0	0	0	0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 12/04

DRAWN BY: ACE/CAD
CHECKED BY: TAE



Rev. 3-1-05

11/20/2004 03:07:33 PM