

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1313.1 B	COOK	193	10

CONTRACT NO. 62878

80% F.P.D. / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE								50/50 LOCAL:STATE PARTICIPATION SFTY-15
				ROADWAY		BRIDGE (ELMHURST)	RETAINING WALLS	SIGNAL ELMHURST	SIGNS	LIGHTING		
				J000-2A	I000-2A	X271-2A	Y007	Y031-1F	Y002-1C	Y030-1E		
X0322141	REMOVE TEMPORARY WOOD POLE	EACH	4	0	0	0	0	0	0	0	4	0
X0322208	TEMPORARY STORM SEWER PLUGS	EACH	3	0	3	0	0	0	0	0	0	0
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	100	0	100	0	0	0	0	0	0	0
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	476	0	476	0	0	0	0	0	0	0
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	63	0	0	63	0	0	0	0	0	0
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	0	0	0	0	0	0	0	6	0
* X0323651	REMOVE AND REINSTALL EXISTING LIGHTING UNIT	EACH	1	0	0	0	0	0	0	0	1	0
* X0323670	PREFORMED DETECTOR LOOP	FOOT	734	0	0	0	0	734	0	0	0	0
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	8	0	0	8	0	0	0	0	0	0
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	587	0	587	0	0	0	0	0	0	0
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	587	0	587	0	0	0	0	0	0	0
X0696000	BRIDGE DRAINAGE SYSTEM	L SUM	1	0	0	1	0	0	0	0	0	0
X0712400	TEMPORARY PAVEMENT	SQ YD	2561	0	2561	0	0	0	0	0	0	0
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	351	351	0	0	0	0	0	0	0	0
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	78	78	0	0	0	0	0	0	0	0
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	12	0	12	0	0	0	0	0	0	0
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	7	0	7	0	0	0	0	0	0	0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	48	48	0	0	0	0	0	0	0	0
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	41	41	0	0	0	0	0	0	0	0
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	581	581	0	0	0	0	0	0	0	0
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	1971	1971	0	0	0	0	0	0	0	0
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	35	35	0	0	0	0	0	0	0	0
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	629	0	629	0	0	0	0	0	0	0
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	36	0	36	0	0	0	0	0	0	0
* X8050010	SERVICE INSTALLATION - GROUND MOUNT	EACH	1	0	0	0	0	1	0	0	0	0
* X8110110	CONDUIT ATTACHED TO STRUCTURE, 1" DIA. GALVANIZED STEEL, PVC COATED	FOOT	475	0	0	0	0	0	0	475	0	0
* X8110121	CONDUIT ATTACHED TO STRUCTURE, 3" DIA. GALVANIZED STEEL, PVC COATED	FOOT	10	0	0	0	0	0	0	10	0	0
* X8110125	CONDUIT ATTACHED TO STRUCTURE, 4" DIA. GALVANIZED STEEL, PVC COATED	FOOT	30	0	0	0	0	0	0	30	0	0
* X8160375	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	4220	0	0	0	0	0	0	4220	0	0
* X8250110	LIGHTING CONTROLLER, RADIO CONTROL, DUPLEX CONSOLE TYPE, WITH SCADA	EACH	1	0	0	0	0	0	0	0	1	0

* SPECIALTY ITEMS

Rev. 3-1-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE 12/04

DRAWN BY ACE/CAD
CHECKED BY TAE



11/18/04 10:00 AM