

SUMMARY OF QUANTITIES

F.A.P. RTE. 305	SECTION 1313.1 B	COUNTY COOK	TOTAL SHEETS 193	SHEET NO. 6
--------------------	---------------------	----------------	---------------------	----------------

80% FED./20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE								50/50 LOCAL STATE PARTICIPATION SFTY-18		
				ROADWAY J000-2A	ROADWAY I000-2A	BRIDGE (ELMHURST) X271-2A	RETAINING WALLS Y007	SIGNAL ELMHURST Y031-1F	SIGNS Y002-1C	LIGHTING Y030-1E				
60102005	PIPE DRAINS 12" (SPECIAL)	FOOT	88	0	0	88	0	0	0	0	0	0		
60107700	PIPE UNDERDRAINS 6"	FOOT	137	0	137	0	0	0	0	0	0	0		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	202	0	0	202	0	0	0	0	0	0		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	18	0	18	0	0	0	0	0	0	0		
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	16	0	16	0	0	0	0	0	0	0		
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	0	1	0	0	0	0	0	0	0		
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	11	0	11	0	0	0	0	0	0	0		
60221500	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 5 FRAME, CLOSED LID	EACH	3	0	3	0	0	0	0	0	0	0		
60224445	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	0	1	0	0	0	0	0	0	0		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	14	14	0	0	0	0	0	0	0	0		
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8	0	0	0	0	0	0	0	0		
60256940	MANHOLES TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1	0	0	0	0	0	0	0	0		
60500040	REMOVING MANHOLES	EACH	5	0	5	0	0	0	0	0	0	0		
60500050	REMOVING CATCH BASINS	EACH	17	0	17	0	0	0	0	0	0	0		
60500060	REMOVING INLETS	EACH	5	0	5	0	0	0	0	0	0	0		
60500105	FILLING MANHOLES	EACH	2	0	2	0	0	0	0	0	0	0		
60500205	FILLING CATCH BASINS	EACH	2	0	2	0	0	0	0	0	0	0		
60600605	CONCRETE CURB, TYPE B	FOOT	168	0	168	0	0	0	0	0	0	0		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	168	0	168	0	0	0	0	0	0	0		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4410	0	4410	0	0	0	0	0	0	0		
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	21820	0	21820	0	0	0	0	0	0	0		
60624600	CORRUGATED MEDIAN	SQ FT	629	0	629	0	0	0	0	0	0	0		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	3113	3113	0	0	0	0	0	0	0	0		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	0	0	0	0	0	0	0	0		
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2	0	0	0	0	0	0	0	0		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	0	0	0	0	0	0	0	0		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2	0	0	0	0	0	0	0	0		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	0	12	0	0	0	0	0	0	0		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0	1	0	0	0	0	0	0	0		
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0	1	0	0	0	0	0	0	0		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE 12/04

DRAWN BY ACE/CAD
CHECKED BY TAE

