

SUMMARY OF QUANTITIES

00% FED. / 20% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY	BRIDGE (ELMHURST)	RETAINING WALLS	SIGNAL ELMHURST	SIGNS	LIGHTING	50/50 LOCAL STATE PARTICIPATION SFTY-ID			
				J000-2A	I000-2A	X271-2A	Y007	Y031-1F	Y002-1C	Y030-1E				
				CONSTRUCTION TYPE CODE										
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	3	0	0	0	0	0	0	0	3	0		
84200700	LIGHTING FOUNDATION REMOVAL	EACH	1	0	0	0	0	0	0	0	1	0		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	0	0	0	0	1	0	0	0	0		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	0	0	0	0	1	0	0	0	0		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1842	0	0	0	0	1842	0	0	0	0		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	4071	0	0	0	0	4071	0	0	0	0		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3760	0	0	0	0	3760	0	0	0	0		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2533	0	0	0	0	2533	0	0	0	0		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2156	0	0	0	0	2156	0	0	0	0		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	73	0	0	0	0	73	0	0	0	0		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	0	0	0	0	2	0	0	0	0		
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1	0	0	0	0	1	0	0	0	0		
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1	0	0	0	0	1	0	0	0	0		
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	0	0	0	0	1	0	0	0	0		
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	3	0	0	0	0	3	0	0	0	0		
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1	0	0	0	0	1	0	0	0	0		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	0	0	0	0	12	0	0	0	0		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	0	0	0	0	4	0	0	0	0		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	82	0	0	0	0	82	0	0	0	0		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	14	0	0	0	0	14	0	0	0	0		
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	0	0	0	0	8	0	0	0	0		
88700200	LIGHT DETECTOR	EACH	4	0	0	0	0	4	0	0	0	0		
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	0	0	0	0	1	0	0	0	0		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	0	0	0	0	8	0	0	0	0		
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2	0	0	0	0	2	0	0	0	0		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	0	0	0	0	1	0	0	0	0		
89502380	REMOVE EXISTING HANDHOLE	EACH	14	0	0	0	0	14	0	0	0	0		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	0	0	0	0	9	0	0	0	0		
X0301199	ANCHOR BOLTS	EACH	100	0	0	100	0	0	0	0	0	0		
X0322080	BUS SHELTER REMOVE AND RELOCATE	EACH	2	0	2	0	0	0	0	0	0	0		

*
[]
[]

[] Y031-3D 100% CITY OF PROSPECT HEIGHTS

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PALATINE ROAD OVER IL 83 (ELMHURST RD.)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 12/04

DRAWN BY: ACE/CAD
CHECKED BY: TAE



Rev.

1378 0011199-01.dwg 12/22/04 03:07:31 PM