

90% FED. 10% STATE SUMMARY OF QUANTITIES

90% FED. 10% STATE

F.A. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
*	**	WINNEBAGO	317 4
STA.		TO STA.	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY ±000-2A
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12,341
* 63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	150
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	12
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	8
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	34
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	18
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	20
63200310	GUARDRAIL REMOVAL	FOOT	10,652
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	3,213
63500105	DELINEATORS	EACH	237
64200105	SHOULDER RUMBLE STRIP	FOOT	130,017
66400305	CHAIN LINK FENCE, 6'	FOOT	2,100
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	15
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	454
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	219,642
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	16,324
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	16,588
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,146
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9,309
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,490
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5,548
* X7800500	POLYUREA PAVEMENT MARKING - LETTERS & SYMBOLS SPECIAL	SQ FT	628
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	143,377
* 78008330	POLYUREA PAVEMENT MARKING TYPE II - LINE 6"	FOOT	15,924
* 78008340	POLYUREA PAVEMENT MARKING TYPE II - LINE 8"	FOOT	16,588
* X7800550	POLYUREA PAVEMENT MARKING - LINE 12" SPECIAL	FOOT	3,146
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,177
78200410	GUARDRAIL MARKERS, TYPE A	EACH	258
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	57

* SPECIALTY ITEMS

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY ±000-2A
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,140
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	850
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	115
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017100	DOWEL BARS	EACH	2,008
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	324
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	78.5
⊙ Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8
⊙ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
⊙ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
⊙ Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	14
Z0075300	TIE BARS	EACH	570
* D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	30
XX003970	CONNECTION TO BRIDGE RAIL	EACH	16
XX004665	BITUMINOUS CONCRETE PAVEMENT "FULL DEPTH" SUPERPAVE, 11 1/2"	SQ YD	2,798
X0320887	POLYMER CONCRETE	CU FT	45
X0321473	PIPE ELBOW, 15"	EACH	2
X0323591	MEDIAN BARRIER SEPARATOR	FOOT	800
* X0324150	WEATHER SENSOR	EACH	3
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	27,834
X4066540	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N105	TON	17,061
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	25,226
X4066750	LEVELING BINDER (HAND METHOD), SUPERPAVE N105	TON	99
X4073116	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 11 3/4"	SQ YD	2,279
X4210307	WIDE FLANGE BEAM TERMINAL JOINT REPAIR (SPECIAL)	EACH	2
X4409420	BITUMINOUS SURFACE REMOVAL 3 1/4"	SQ YD	24,635
X6330115	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, REMOVE AND RELOCATE	EACH	4
X7010540	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331 (SPECIAL)	L SUM	1
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	45
X7040305	TEMPORARY CONCRETE BARRIER, TERMINAL SECTION (SPECIAL)	EACH	1
X8324914	SLOTTED DRAINS TO BE ADJUSTED	FOOT	68
X4066640	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-9.5, N105	TON	4,878

* SPECIALTY ITEMS
 ⊙ SFTY-3N

PLT DATE = Thu Jun 06 14:27:43 2005
 FILE NAME = c:\projects\2025000\1225000-vr.dgn
 PLOT SCALE = 50.0000 / IN.
 REFERENCE = #REF*