

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

20100500 TREE REMOVAL, ACRES
 ACRE LOCATION
 US 20 WESTBOUND
 2651 + 87 TO 2656 + 38 RIGHT
 TOTAL 0.94

20200600 EXCAVATING AND GRADING EXISTING SHOULDER
 UNIT LOCATION
 RAMP AD
 11.35 52 + 50 TO 63 + 85 RIGHT
 11.35 52 + 50 TO 63 + 85 LEFT
 20.91 65 + 22 TO 86 + 13 RIGHT
 17.71 65 + 27 TO 82 + 98 LEFT
 RAMP BD
 24.30 25 + 00 TO 49 + 30 RIGHT
 20.00 29 + 30 TO 49 + 30 LEFT
 12.57 53 + 33 TO 65 + 90 RIGHT
 12.57 53 + 33 TO 65 + 90 LEFT
 6.91 67 + 44 TO 74 + 35 RIGHT
 6.36 67 + 44 TO 73 + 80 LEFT
 15.00 75 + 35 TO 90 + 35 RIGHT
 12.27 74 + 90 TO 87 + 17 LEFT
 RAMP DB
 16.42 31 + 00 TO 47 + 42 RIGHT
 10.76 36 + 66 TO 47 + 42 LEFT
 22.17 48 + 95 TO 71 + 12 RIGHT
 16.05 48 + 95 TO 65 + 00 LEFT
 TOTAL 236.70

20201400 SUB-BASE GRANULAR MATERIAL, TYPE A
 TON LOCATION
 US 20 EASTBOUND
 2652 + 43 TO 2676 + 14 TEMP WIDENING
 TOTAL 2,390

21400100 GRADING AND SHAPING DITCHES
 FOOT LOCATION
 US 20 EASTBOUND
 2666 + 00 TO 2666 + 75 RIGHT
 TOTAL 75

28000300 TEMPORARY DITCH CHECKS
 EACH LOCATION
 1 2662 + 00 MEDIAN
 1 2667 + 50 MEDIAN
 TOTAL 2

28000400 PERIMETER EROSION BARRIER
 FOOT LOCATION
 US 20 WESTBOUND
 2651 + 87 TO 2656 + 38 RIGHT
 451
 US 20 EASTBOUND
 2661 + 00 TO 2670 + 50 RIGHT
 950
 RAMP AD
 8,450 52 + 51 TO 98 + 07 RIGHT & LEFT
 RAMP BD
 11,248 25 + 00 TO 90 + 36 RIGHT & LEFT
 RAMP DB
 7,923 31 + 00 TO 72 + 15 RIGHT & LEFT
 TOTAL 29,022

28000500 INLET AND PIPE PROTECTION
 EACH LOCATION
 1 718 + 90 MEDIAN INLET
 1 2583 + 00 MEDIAN INLET
 1 2585 + 75 MEDIAN INLET
 1 2604 + 50 MEDIAN INLET
 1 2632 + 90 MEDIAN INLET
 1 2656 + 75 TEMP CULVERT
 1 2656 + 90 MEDIAN INLET
 1 2664 + 50 MEDIAN INLET
 1 2666 + 75 MEDIAN INLET
 1 2672 + 30 MEDIAN INLET
 1 2734 + 50 MEDIAN INLET
 TOTAL 11

28200100 FILTER FABRIC FOR USE WITH RIPRAP
 SQ YD LOCATION
 US 20 EASTBOUND
 2663 + 15 TO 2664 + 00 RIGHT
 TOTAL 89

28300400 AGGREGATE DITCH
 TONS LOCATION
 US 20 EASTBOUND
 2663 + 15 TO 2664 + 00 RIGHT
 TOTAL 61

35100100 AGGREGATE BASE COURSE, TYPE A
 TON LOCATION
 253.42 2525 + 70 MEDIAN CROSSOVER
 82.00 2735 + 55 MEDIAN CROSSOVER
 TOTAL 335.42

40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT
 SQ YD LOCATION
 88.89 2430 + 69 TO 2431 + 19 SHOULDER NB 39 @ Kishwaukee RIVER BRIDGE
 88.89 2466 + 61 TO 2467 + 11 SHOULDER NB 39 @ BLACKHAWK ROAD
 88.89 2469 + 16 TO 2469 + 66 SHOULDER NB 39 @ BLACKHAWK ROAD
 88.89 2550 + 54 TO 2551 + 04 SHOULDER NB 39 @ STRUCTURE OVER RAMP BD
 88.89 2554 + 79 TO 2555 + 29 SHOULDER NB 39 @ STRUCTURE OVER RAMP BD
 88.89 2557 + 79 TO 2558 + 29 SHOULDER NB 39 @ LINDEN ROAD
 88.89 2560 + 59 TO 2561 + 09 SHOULDER NB 39 @ LINDEN ROAD
 88.89 2569 + 69 TO 2570 + 19 SHOULDER NB 39 @ STRUCTURE OVER US 20
 88.89 2431 + 56 TO 2432 + 06 SHOULDER SB 39 @ KISHWAUKEE RIVER BRIDGE
 88.89 2466 + 62 TO 2467 + 12 SHOULDER SB 39 @ BLACKHAWK ROAD
 88.89 2469 + 16 TO 2469 + 66 SHOULDER SB 39 @ BLACKHAWK ROAD
 88.89 63 + 13 TO 63 + 63 SHOULDER Ramp AD @ LINDEN ROAD
 88.89 65 + 44 TO 65 + 94 SHOULDER Ramp AD @ LINDEN ROAD
 88.89 46 + 66 TO 47 + 16 SHOULDER Ramp DB @ LINDEN ROAD
 88.89 49 + 19 TO 49 + 69 SHOULDER Ramp DB @ LINDEN ROAD
 88.89 48 + 29 TO 48 + 79 SHOULDER Ramp BD @ STRUCTURE OVER US 20
 88.89 53 + 59 TO 54 + 09 SHOULDER Ramp BD @ STRUCTURE OVER US 20
 88.89 65 + 14 TO 65 + 64 SHOULDER Ramp BD @ LINDEN ROAD
 88.89 67 + 70 TO 68 + 20 SHOULDER Ramp BD @ LINDEN ROAD
 88.89 72 + 55 TO 73 + 05 SHOULDER Ramp BD @ OMISSION UNDER I-39
 88.89 75 + 74 TO 76 + 24 SHOULDER Ramp BD @ OMISSION UNDER I-39
 211.11 705 + 66 TO 706 + 16 EASTBOUND US 20
 211.11 2646 + 01 TO 2646 + 51 NORTHBOUND 39/EASTBOUND US 20
 211.11 2650 + 15 TO 2650 + 65 NORTHBOUND 39/EASTBOUND US 20
 211.11 2682 + 05 TO 2682 + 55 NORTHBOUND 39/EASTBOUND US 20
 216.67 2687 + 32 TO 2687 + 82 NORTHBOUND 39/EASTBOUND US 20
 300.00 2721 + 84 TO 2722 + 34 NORTHBOUND 39/EASTBOUND US 20
 300.00 2726 + 57 TO 2727 + 07 NORTHBOUND 39/EASTBOUND US 20
 316.67 2744 + 83 TO 2745 + 33 NORTHBOUND 39/EASTBOUND US 20
 211.11 705 + 66 TO 706 + 16 WESTBOUND US 20
 211.11 2645 + 73 TO 2646 + 23 SOUTHBOUND 39/ WESTBOUND US 20
 211.11 2649 + 92 TO 2650 + 42 SOUTHBOUND 39/ WESTBOUND US 20
 211.11 2680 + 92 TO 2681 + 42 SOUTHBOUND 39/ WESTBOUND US 20
 211.11 2686 + 18 TO 2686 + 68 SOUTHBOUND 39/ WESTBOUND US 20
 300.00 2721 + 50 TO 2722 + 00 SOUTHBOUND 39/ WESTBOUND US 20
 183.33 2725 + 28 TO 2725 + 78 SOUTHBOUND 39/ WESTBOUND US 20
 211.11 2744 + 83 TO 2745 + 33 SOUTHBOUND 39/ WESTBOUND US 20
 155.56 52 + 51 TO 53 + 01 Ramp AD
 155.56 2711 + 78 TO 2712 + 28 Ramp from EB Harrison Ave. to SB I-39
 166.67 2712 + 44 TO 2712 + 94 Ramp NB I-39 to EB US 20
 155.56 2718 + 24 TO 2718 + 74 Ramp SB I-39 to EB US 20
 144.44 2721 + 42 TO 2721 + 92 Ramp from EB Harrison Ave. to NB I-39
 166.67 2728 + 17 TO 2728 + 67 Ramp NB I-39 to WB Harrison Ave
 166.67 2733 + 50 TO 2734 + 00 Ramp from WB US 20 to NB I-39
 122.22 2573 + 90 TO 2574 + 40 Ramp from Ramp DA to WB US 20
 TOTAL 6,827.78

PLOT DATE = Fri, Jan 07 07:55:08 2005
 FILE NAME = S:\2005\64596\022000.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = *REF#