

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

70300240	TEMPORARY PAVEMENT MARKING	- LINE 6"
FOOT	LOCATION	
400.0	STAGE II 2645 + 25 TO 2649 + 25	WHITE CENTERLINE
<b>NORTH BOUND</b>		
2,551.5	2430 + 44 TO 2532 + 50	White Skip Dash
885.0	2561 + 60 TO 2570 + 45	White
348.3	705 + 66 TO 719 + 59	White Skip Dash
4,341.9	2571 + 66 TO 2745 + 34	White Skip Dash
480.5	2593 + 13 TO 2612 + 35	White Skip Dash
<b>SOUTH BOUND</b>		
1,990.0	2431 + 30 TO 2510 + 90	White Skip Dash
340.8	705 + 66 TO 719 + 59	White Skip Dash
4,341.9	2571 + 66 TO 2745 + 34	White Skip Dash
643.5	2610 + 30 TO 2636 + 04	White Skip Dash
<b>TOTAL</b>	<b>16,323.3</b>	

70300250	TEMPORARY PAVEMENT MARKING	- LINE 8"
FOOT	LOCATION	
<b>NORTH BOUND</b>		
2,486.0	2523 + 00 TO 2547 + 86	White
3,900.0	2523 + 00 TO 2562 + 00	White
1,161.0	2558 + 84 TO 2570 + 45	Yellow
<b>SOUTH BOUND</b>		
1,710.0	2510 + 90 TO 2528 + 00	Yellow
4,335.3	2494 + 78 TO 86 + 13	White
3,035.0	2510 + 90 TO 82 + 97	White
<b>TOTAL</b>	<b>16,627.3</b>	

70300260	TEMPORARY PAVEMENT MARKING	- LINE 12"
FOOT	LOCATION	
<b>NORTH BOUND</b>		
100	2566 + 50 TO 2570 + 45	Yellow Diagonals
1,300	2528 + 00 TO 2562 + 00	White Chevrons & Diagonals
160	2709 + 21 TO 2712 + 75	White Chevrons
60	2721 + 46 TO 2722 + 04	White Chevrons
60	2727 + 71 TO 2729 + 00	White Chevrons
60	2733 + 53 TO 2734 + 46	White Chevrons
<b>SOUTH BOUND</b>		
509	2496 + 00 TO 2514 + 50	White Diagonals
617	2512 + 50 TO 2526 + 00	Yellow Diagonals
60	2710 + 30 TO 2711 + 47	White Chevrons
60	2719 + 53 TO 2721 + 02	White Chevrons
60	2726 + 53 TO 2727 + 16	White Chevrons
100	2735 + 47 TO 2738 + 63	White Chevrons
<b>TOTAL</b>	<b>3,146</b>	

70301000	WORK ZONE PAVEMENT MARKING REMOVAL	
SQ FT	LOCATION	
2,850	2651 + 25 TO 2680 + 04	STAGE I
3,906	2645 + 25 TO 2679 + 04	STAGE II
2,553	2659 + 54 TO 2671 + 04	STAGE III
<b>TOTAL</b>	<b>9,309</b>	

70400100	TEMPORARY CONCRETE BARRIER	
FOOT	LOCATION	
2,490	2652 + 24 TO 2677 + 14	STAGE I
<b>TOTAL</b>	<b>2,490</b>	

70400200	RELOCATE TEMPORARY CONCRETE BARRIER	
FOOT	LOCATION	
1,908	2661 + 00 TO 2670 + 54	STAGE II
1,150	2659 + 54 TO 2671 + 04	STAGE III
2,490	2652 + 24 TO 2677 + 14	STAGE IV
<b>TOTAL</b>	<b>5,548</b>	

78008300	POLYUREA PAVEMENT MARKING TYPE II - LETTERS & SYMBOLS	
SQ FT	LOCATION	
66	2588 + 00 TO 2601 + 20	EB20 AERIAL SPEED CHECK
54	2674 + 00 TO 2687 + 20	EB20 AERIAL SPEED CHECK
54	2681 + 80 TO 2695 + 00	WB20 AERIAL SPEED CHECK
42	2596 + 50	EB 20
42	2601 + 00	EB 20
42	2605 + 00	EB 20
42	2610 + 00	EB 20
23	90 + 00	RAMP AD
23	97 + 00	RAMP AD
23	2520 + 20	SB MAINLINE
9.8	2626 + 16	DRIVING LANE
22.7	2625 + 58	DRIVING LANE
23.1	2625 + 00	DRIVING LANE
9.8	2618 + 16	DRIVING LANE
22.7	2617 + 58	DRIVING LANE
23.1	2617 + 00	DRIVING LANE
9.8	2634 + 16	AUX. LANE
27.1	2633 + 58	AUX. LANE
15.9	2633 + 00	AUX. LANE
9.8	2621 + 16	AUX. LANE
27.1	2620 + 58	AUX. LANE
15.9	2620 + 00	AUX. LANE
<b>TOTAL</b>	<b>627.8</b>	

78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	
FOOT	LOCATION	
<b>NORTH BOUND</b>		
11,344.0	2430 + 44 TO 2543 + 88	White Edge Line Right
12,840.0	2430 + 44 TO 2558 + 84	Yellow Edge Line Left
1,393.0	705 + 66 TO 719 + 59	White Edge Line Right
1,393.0	705 + 66 TO 719 + 59	Yellow Edge Line Left
17,367.6	2571 + 66 TO 2745 + 34	Yellow Edge Line Left
2,147.0	2571 + 66 TO 2593 + 13	White Edge Line Right
11,930.0	2596 + 00 TO 2713 + 50	White Edge Line Right
354.0	2709 + 21 TO 2712 + 75	White Edge Line Right
75.0	2712 + 75 TO 2713 + 50	Yellow Edge Line Right
1,282.0	2709 + 21 TO 2722 + 03	White Edge Line Right
57.0	2721 + 46 TO 2722 + 03	White Edge Line Right
760.0	2722 + 00 TO 2729 + 60	White Edge Line Right
182.0	2727 + 21 TO 2729 + 03	White Edge Line Right
725.0	2727 + 21 TO 2734 + 46	White Edge Line Right
146.0	2733 + 00 TO 2734 + 46	White Edge Line Right
1,236.6	2733 + 00 TO 2745 + 37	White Edge Line Right
<b>SUBTOTAL</b>	<b>63,232.3</b>	
<b>SOUTH BOUND</b>		
7,960.0	2431 + 30 TO 2510 + 90	Yellow Edge Line Left
6,347.7	2431 + 30 TO 2494 + 78	White Edge Line Right
1,363.0	705 + 66 TO 719 + 59	White Edge Line Right
1,363.0	705 + 66 TO 719 + 59	Yellow Edge Line Left
17,367.6	2571 + 66 TO 2745 + 34	Yellow Edge Line Left
3,864.0	2571 + 66 TO 2610 + 30	White Edge Line Right
10,200.0	2610 + 30 TO 2712 + 30	White Edge Line Right
117.0	2710 + 30 TO 2711 + 47	White Edge Line Right
1,072.0	2710 + 30 TO 2721 + 02	White Edge Line Right
149.0	2719 + 53 TO 2721 + 02	White Edge Line Right
551.0	2721 + 02 TO 2726 + 53	White Edge Line Right
63.0	2726 + 53 TO 2727 + 16	White Edge Line Right
1,210.0	2726 + 53 TO 2738 + 63	White Edge Line Right
316.0	2735 + 47 TO 2738 + 63	White Edge Line Right
147.0	2734 + 00 TO 2735 + 47	Yellow Edge Line Right
1,133.6	2734 + 00 TO 2745 + 34	White Edge Line Right
<b>SUBTOTAL</b>	<b>53,223.9</b>	
<b>RAMP D B</b>		
4,100.0	31 + 00 TO 72 + 00	White Edge Line Right
3,000.0	35 + 00 TO 65 + 00	Yellow Edge Line Left
415.0	65 + 00 TO 69 + 15	White Edge Line Left
<b>SUBTOTAL</b>	<b>7,515.0</b>	
<b>RAMP A D</b>		
3,243.0	53 + 70 TO 86 + 13	White Edge Line Right
2,927.0	53 + 70 TO 82 + 97	Yellow Edge Line Left
<b>SUBTOTAL</b>	<b>6,170.0</b>	
<b>RAMP B D</b>		
6,537.0	25 + 00 TO 90 + 37	White Edge Line Right
6,698.0	29 + 28 TO 96 + 26	Yellow Edge Line Left
<b>SUBTOTAL</b>	<b>13,235.0</b>	
<b>TOTAL</b>	<b>143,376.2</b>	

PLOT DATE = Fri, Jan 07, 07:26:38 2006  
 FILE NAME = C:\projects\212500\122500.dgn  
 PLOT SCALE = 50.0000 / 1 IN.  
 REFERENCE = #REF#