

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WINNEBAGO	317	43
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK & SEEDING SCHEDULE

EARTHWORK SCHEDULE					
LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)	
	CU YD	CU YD	CU YD	CU YD	
US 20 - PAVEMENT REPLACEMENT					
STAGE 1					
2652 + 50 - 2676 + 00	2226	1670	359	1311	
STAGE 2					
2662 + 00 - 2670 + 50	382	286	0	286	
STAGE 3					
2662 + 00 - 2670 + 50	463	347	21	326	
STAGE 4					
2652 + 50 - 2676 + 00	1443	1082	1876	-794	
I-39/US 20 - GUARDRAIL INSTALLATIONS					
2572 + 00 - 2573 + 00	0	0	36	-36	
2583 + 50 - 2585 + 50	0	0	49	-49	
2604 + 50 - 2610 + 50	2	292	0	292	
2632 + 00 - 2636 + 50	17	13	173	-160	
2692 + 00 - 2697 + 00	0	0	173	-173	
2735 + 50 - 2739 + 50	339	254	27	227	
RAMPS					
RAMP AD					
50 + 00 - 85 + 50	92	69	1269	-1200	
RAMP BD					
25 + 00 - 89 + 00	164	123	1940	-1817	
RAMP DB					
31 + 00 - 71 + 00	71	53	1122	-1069	
ESTIMATED EARTHWORK					
I-39/US 20 - MEDIAN CROSSOVER REMOVAL AREAS					
711 + 20	31	23	0	23	
719 + 00	30	22	0	22	
2598 + 50	42	31	0	31	
2606 + 50	38	29	0	29	
2632 + 75	36	27	0	27	
2657 + 25	73	55	0	55	
2735 + 55	32	24	0	24	
I-39/US 20 - SHOULDER WIDENING					
2726 + 6 - 2739 + 78	248	186	0	186	
I-39/US 20 - MISCELLANEOUS AREAS					
2430 + 44 - 2738 + 79	237	178	453	-275	
TOTAL	5965	4765	7498	-2733	

SEEDING SCHEDULE						
LOCATION	REMARKS	Totals - Left and Right				
		SEEDING CLASS 2A ACRES	NITROGEN FERTILIZER NUTRIENT LBS	PHOSPHORUS FERTILIZER NUTRIENT LBS	POTASSIUM FERTILIZER NUTRIENT LBS	EROSION CONTROL BLANKET SQ YD
I-39/US 20						
2572+00.00 TO 2573+00.00		0.06	5.4	5.4	5.4	290.4
2583+50.00 TO 2585+50.00		0.08	7.2	7.2	7.2	387.2
2604+50.00 TO 2610+50.00		0.41	36.9	36.9	36.9	1,984.4
2632+00.00 TO 2636+50.00		0.33	29.7	29.7	29.7	1,597.2
2651+87.00 TO 2656+38.00	LEFT - TREE REMOVAL AREA	0.94	84.6	84.6	84.6	4549.6
2652+50.00 TO 2676+00.00		0.53	47.7	47.7	47.7	2,565.2
2692+00.00 TO 2697+00.00		0.36	32.4	32.4	32.4	1,742.4
2735+50.00 TO 2739+50.00	CURB REMOVAL AREA	0.27	24.3	24.3	24.3	1,306.8
Ramp AD						
46+00.00 TO 85+50.00		2.37	213.3	213.3	213.3	11,470.8
Ramp DB						
31+00.00 TO 71+00.00		1.94	174.6	174.6	174.6	9,389.6
Ramp BD						
25+00.00 TO 89+00.00		3.50	315.0	315.0	315.0	16,940.0
I-39/US 20 - ESTIMATED QUANTITIES						
2430+44.00 TO 2745+33.63	MISC. AREAS	9.04	813.6	813.6	813.6	43,753.6
TOTALS		19.83	1784.70	1784.70	1784.70	95977.20

PLOT DATE = Thu Dec 23 13:46:46 2024
 FILE NAME = C:\p\proj\212590\212590.dwg
 PLOT SCALE = 50.0000 : 1 IN.
 REFERENCE = WIER#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY