



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

03/04/2005

SUBJECT: FAP Route 595
Section 1-3-K
Rock Island County
Contract No. 64647
Item No. 69, 3/11/05 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised Sheets 17 & 311 of the Plans.
3. Revised page iii of the Table of Contents to the Special Provisions.
4. Revised page 155 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'DE' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Gregg Mounts; Roger Driskell; Jim White; Design & Environment File

MS/cah

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 64647

State Job # - C-92-041-05
 PPS NBR - 2-95140-0200
 County Name - ROCK ISLAND - -
 Code - 161 - -
 District - 2 - -
 Section Number - 1-3-K

Project Number

Route
 FAP 595

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
** DELETED							
XX000739	CURB STOP & BOX 1	EACH	1.000				
XX002909	CLASS SI CONC	CU YD	9.100				
XX003216	UD #36 #6G XLPUSE1.25	FOOT	972.000				
XX003711	BUS SHELTER REMOVAL	EACH	1.000				
XX003786	PLUG MJ 8	EACH	2.000				
XX003788	BEND DIMJ 90 DEG 8	EACH	2.000				
XX003789	BEND DIMJ 11-1/4 8	EACH	2.000				
XX003790	TEE DIMJ, 8X2	EACH	1.000				
XX003792	TEE DIMJ, 8X6	EACH	3.000				
XX003795	V GATE, 8 MJRW & BOX	EACH	2.000				
XX003796	TAP & CORP. 1"	EACH	3.000				
XX003799	COPPER SERVICE TK 1	FOOT	103.000		**		
XX003800	SAN S DIP PCL 350 12	FOOT	716.000				
XX003802	SAN S DIP PCL 350 8	FOOT	1,055.000				
** REVISED : MARCH 3, 2005							

LIGHT EMITTING DIODE (LED) SIGNAL HEAD (BDE)..... 61

MULCHING SEEDED AREAS (BDE)..... 63

ORGANIC ZINC RICH PAINT SYSTEM 64

PARTIAL PAYMENTS (BDE)..... 67

PAYMENTS TO SUBCONTRACTORS (BDE)..... 68

PERSONAL PROTECTIVE EQUIPMENT (BDE)..... 69

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE)..... 69

POLYUREA PAVEMENT MARKING (BDE) 70

PORTABLE CHANGEABLE MESSAGE SIGNS (BDE)..... 76

PORTLAND CEMENT (BDE)..... 77

PORTLAND CEMENT CONCRETE (BDE)..... 77

PRECAST CONCRETE PRODUCTS (BDE) 78

RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE)..... 79

SEEDING AND SODDING (BDE) 82

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 84

SHOULDER STABILIZATION AT GUARDRAIL (BDE) 86

STEEL COST ADJUSTMENT (BDE) 86

SUBGRADE PREPARATION (BDE)..... 89

SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE)..... 89

TEMPORARY EROSION CONTROL (BDE)..... 95

TRAFFIC BARRIER TERMINALS (BDE)..... 96

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)..... 97

TRANSIENT VOLTAGE SURGE SUPPRESSION (BDE) 98

TRUCK BED RELEASE AGENT (BDE)..... 99

UNDERDRAIN OPERATIONS (BDE) 100

WEIGHT CONTROL DEFICIENCY DEDUCTION 100

WORK ZONE SPEED LIMIT SIGNS (BDE)..... 101

WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 102

CLEANING AND PAINTING NEW METAL STRUCTURES 103

FABRIC REINFORCED ELASTOMERIC MAT 109

PROJECT LABOR AGREEMENT..... 110

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 123

STORM WATER POLLUTION PREVENTION PLAN 130

404 PERMIT 138

PAVEMENT THICKNESS DETERMINATION FOR PAYMENT (BDE)..... 146

SLIPFORM PARAPET..... 152

SEEDING, CLASS 7 SPECIAL 155

Additional cores may be required to determine the longitudinal extent of removal and replacement if it can not be determined and agreed upon by other means (i.e. visual, sounding, non-destructive testing, etc.).

Any parapet section with more than one half of its length rejected or with remaining segments less than 3m (10 feet) in length shall be removed and replaced in its entirety.

If reinforcement bars are damaged during the removal and replacement, additional removal and replacement shall be done, as necessary, to ensure minimum splice length of replacement bars. Any damage to epoxy coating of bars shall be repaired according to Article 508.05.

All core holes will be filled with a non-shrink grout meeting the requirements of Section 1024.

SEEDING, CLASS 7 SPECIAL

Effective January 10, 2004

This work shall be done in accordance with applicable portions of Section 250 of the Standard Specifications and shall be applied to all areas designated on the plans or specifications.

Seeding Class 7, Special shall consist of the following:

Common Name	Quantity/Acre
Kentucky Bluegrass	50 lbs.
Annual Rye	15 lbs.
Oats	40 lbs.

Seeding Class 7, Special shall be sown for erosion control as soon as all of the earth is excavated from the site and the specified grading and shaping are completed.

Method of Measurement: Seeding Class 7, Special will be measured as specified in Article 250.08 of the Standard Specifications, in acres of surface area seeded.

Basis of Payment: Seeding Class 7, Special will be paid for at the contract unit price per acre of SEEDING CLASS 7, SPECIAL, as specified.

Revised 3/4/05