

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE
				J000-2A	SFTY-3N	X028-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C
				QUANTITY	P. C. CONCRETE	IMPACT ATTEN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FT.	531	531										
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FT.	68	68										
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FT.	3,992	3,992										
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FT.	1,070	1,070										
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FT.	706	706										
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FT.	770	770										
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FT.	180	180										
55100500	STORM SEWER REMOVAL 12"	FT.	1,681	1,681										
55100700	STORM SEWER REMOVAL 15"	FT.	220	220										
55100900	STORM SEWER REMOVAL 18"	FT.	282	282										
55101200	STORM SEWER REMOVAL 24"	FT.	745	745										
55101600	STORM SEWER REMOVAL 36"	FT.	531	531										
*56103000	DUCTILE IRON WATER MAIN 6"	FT.	30	30										
*56103100	DUCTILE IRON WATER MAIN 8"	FT.	978	978										
*56103300	DUCTILE IRON WATER MAIN 12"	FT.	938	938										
*56105750	BUTTERFLY VALVES 12"	EACH	2	2										
*56201600	CORPORATION STOPS 1 1/2"	UNIT	1	1										
*56201800	CORPORATION STOPS 2"	EACH	3	3										
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1										
*56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	3	3										
*56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6	6										

\* SPECIALTY ITEMS