

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	49

  

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FT.	
	MILAN BELTWAY STA. 362+80-364+00 RT. STA. 364+00	107 37	
	JOHN DEERE ROAD STA. 386+00-388+25 STA. 388+25-390+50	222 222	
	BLACKHAWK ROAD RT. STA. 1147+85-1148+50 LT. STA. 1153+52-1153+98 LT. STA. 1154+20-1154+00	56 62 46	
	52ND AVENUE LT. STA. 1174+15-RT. STA. 1174+25 RT. STA. 1174+25-211+75	84 122	
	VALLEY VIEW STA. 168+64.2	30	
	RELOCATED THIRD STREET STA. 2+25-3+14.53	82	
	<b>TOTAL</b>	<b>1,070</b>	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FT.	
	JOHN DEERE ROAD STA. 388+25-390+50	222	
	BLACKHAWK ROAD RT. STA. 1147+21.4-1147+85	62	
	52ND AVENUE RT. STA. 1173+00-1174+25 RT. STA. 217+00-218+94.5	122 190	
	VALLEY VIEW RT. STA. 167+66.37-168+64.2 LT. STA. 168+54.5-168+64.2	96 14	
	<b>TOTAL</b>	<b>706</b>	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FT.	
	JOHN DEERE ROAD RT. STA. 388+25	76	
	52ND AVENUE RT. STA. 1170+01.14-1171+75 RT. STA. 1171+75-1173+00	176 122	
	RELOCATED THIRD STREET LT. STA. 3+14.53-4+00 STA. 5+00 RT. STA. 5+00-7+50 RT. STA. 7+50	72 30 248 46	
	<b>TOTAL</b>	<b>770</b>	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FT.	
	VALLEY VIEW LT. STA. 152+10.82-RT. STA. 152+22 LT. STA. 152+10.82-152+14.00 RT. STA. 152+22.00-152+27.50 RT. STA. 152+28.50+152+58.00	60 19 7 34	
	RELOCATED THIRD STREET RT. STA. 9+42.5-10+00	60	
	<b>TOTAL</b>	<b>180</b>	
55100500	STORM SEWER REMOVAL 12" (CONT.)	FT.	
	VALLEY VIEW RT. STA. 152+37-152+56 RT. STA. 154+40 RT. STA. 157+02 RT. STA. 157+62 RT. STA. 159+25 RT. STA. 162+41 LT. STA. 162+52 RT. STA. 164+97 RT. STA. 169+73-169+92 RT. STA. 170+15-LT. STA. 171+17 AR. STA. 171+17	40 38 42 42 54 57 38 30 26 102 24	
	OLD BLACKHAWK ROAD RT. STA. 1+16-1+29 RT. STA. 1+31-1+52	16 28	
	RELOCATED THIRD STREET LT. & RT. STA. 1+78 LT. STA. 1+78-0+83	38 260	
	<b>TOTAL</b>	<b>1,681</b>	
55100700	STORM SEWER REMOVAL 15"	FT.	
	52ND AVENUE LT. STA. 1174+13-1174+46	46	
	VALLEY VIEW RT. STA. 168+96-169+71 RT. STA. 169+75-170+12	126 48	
	<b>TOTAL</b>	<b>220</b>	
55100900	STORM SEWER REMOVAL, 18"	FT.	
	52ND AVENUE LT. STA. 1164+53-1164+70 AR. STA. 216+94 RT. STA. 216+95-218+93	24 36 198	
	RELOCATED 3RD STREET AR. STA. 3+05	24	
	<b>TOTAL</b>	<b>282</b>	
55101200	STORM SEWER REMOVAL 24"	FT.	
	52ND AVENUE LT. STA. 1164+72-1164+85 RT. STA. 1170+23-1174+10 RT. STA. 1174+12-LT. STA. 1174+13	12 410 35	
	RELOCATED THIRD STREET LT. STA. 3+05-3+08 LT. STA. 3+09-LT. STA. 1164+90 (52ND AVE.)	10 278	
	<b>TOTAL</b>	<b>745</b>	
55101600	STORM SEWER REMOVAL 36"	FT.	
	52ND AVENUE LT. STA. 1164+93-1167+40 LT. STA. 1167+42-1169+57	242 212	
	TRINITY DRIVE AR. STA. 1+64 LT. STA. 1+64	21 56	
	<b>TOTAL</b>	<b>531</b>	
56103000	DUCTILE IRON WATER MAIN 6"	FT.	
	52ND AVENUE 85.06' LT. STA. 1173+37.17-80.59' LT. STA. 1173+34.78 43.35' LT. STA. 218+00-38.35' LT. STA. 218+00 60.67' LT. STA. 213+50.02-55.67' LT. STA. 213+50.02	5 5 5	
	RELOCATED THIRD STREET 23.73' RT. STA. -0+66.54-28.73' RT. STA. -0+66.54 23.58' LT. STA. 10+46.24-27.31' RT. STA. 10+49.78 20.31' RT. STA. 3+77.02-24.19' RT. STA. 3+79.89	5 5 5	
	<b>TOTAL</b>	<b>30</b>	
56103100	DUCTILE IRON WATER MAIN 8"	FT.	
	JOHN DEERE ROAD RT. STA. 409+00-410+00	35	
	RELOCATED THIRD STREET 29.58' RT. STA. 3+67.63-38.76' RT. STA. 0+92.73 (TRINITY)	943	
	<b>TOTAL</b>	<b>978</b>	
56103300	DUCTILE IRON WATER MAIN 12"	FT.	
	TRINITY DRIVE 38.76' RT. STA. 0+92.73-26.14' LT. STA. 218+53.45 (52ND AVE.)	938	
	<b>TOTAL</b>	<b>938</b>	
56105750	BUTTERFLY VALVES 12"	EACH	
	TRINITY DRIVE 46.59' RT. STA. 0+95.88-87.64' LT. STA. 1173+31.70 (52ND AVE.)	2	
	<b>TOTAL</b>	<b>2</b>	
56201600	CORPORATION STOPS 1 1/2"	UNIT	
	TRINITY DRIVE 28.26' RT. STA. 0+89.86	1	
	<b>TOTAL</b>	<b>1</b>	
56201800	CORPORATION STOPS 2"	EACH	
	52ND AVENUE LT. STA. 218+50	1	
	RELOCATED THIRD STREET 29.58' RT. STA. 3+67.63-32.23' LT. STA. 218+47.31 (52ND AVE.)	2	
	<b>TOTAL</b>	<b>3</b>	
56400100	FIRE HYDRANTS TO BE MOVED	EACH	
	44TH STREET CONNECTOR RT. STA. 2+08	1	
	<b>TOTAL</b>	<b>1</b>	
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	
	BLACKHAWK ROAD LT. STA. 1147+00	1	
	44TH STREET RT. STA. 16+76 LT. STA. 19+22	1 1	
	<b>TOTAL</b>	<b>3</b>	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	
	MILAN BELTWAY 19.02' LT. STA. 404+60.54	1	
	52ND AVENUE 23.31' LT. STA. 1165+49.81 26.31' LT. STA. 1169+03.31 49.17' LT. STA. 1172+95.39 30.19' LT. STA. 212+66.31 29.29' LT. STA. 216+37.71	1 1 1 1 1	
	<b>TOTAL</b>	<b>6</b>	
56400600	FIRE HYDRANTS	EACH	
	52ND AVENUE 79.72' LT. STA. 1173+34.32 54.51' LT. STA. 213+49.78 37.37' LT. STA. 217+99.77	1 1 1	
	RELOCATED THIRD STREET 36.23' RT. STA. -0+66.54 24.93' RT. STA. 3+80.42 28.07' LT. STA. 10+50.44	1 1 1	
	<b>TOTAL</b>	<b>6</b>	
56400800	FIRE HYDRANT AND VALVE TO BE MOVED	EACH	
	VALLEY VIEW LT. STA. 166+46	1	
	<b>TOTAL</b>	<b>1</b>	