

FAP RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
840	(1392-DI)	KANKAKEE	24	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #66131

SUMMARY OF QUANTITIES				URBAN	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE: X028-2A	
				EX SN 046-C802	PR SN 046-2015
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	24	
20200100	EARTH EXCAVATION	CU YD	1075	1075	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	380	380	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	703	703	
20800150	TRENCH BACKFILL	CU YD	30	30	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4	
20500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	21	21	
* 25200110	SODDING, SALT TOLERANT	SQ YD	310	310	
* 25200200	SUPPLEMENTAL WATERING	UNIT	0.9	0.9	
28100107	STONE RIPRAP, CLASS A4	SQ YD	83	83	
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	83	83	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	323	323	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	62	62	
40600990	TEMPORARY RAMP	SQ YD	64	64	
42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	22	22	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1417	1417	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	465	465	
44000100	PAVEMENT REMOVAL	SQ YD	311	311	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	240	240	
44000600	SIDEWALK REMOVAL	SQ FT	1417	1417	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
51500100	NAME PLATES	EACH	1	1	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1	
54020909	PRECAST CONCRETE BOX CULVERT 9' X 9' (M273)	FOOT	120	120	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	4	4	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	44	44	
55100300	STORM SEWER REMOVAL 8"	FOOT	33	33	
55100700	STORM SEWER REMOVAL 15"	FOOT	3	3	
55101200	STORM SEWER REMOVAL 24"	FOOT	54	54	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60222100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 12 FRAME AND GRATE	EACH	1	1	
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EACH	1	1	
60500060	REMOVING INLETS	EACH	2	2	
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	240	240	

SUMMARY OF QUANTITIES				URBAN	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE: X028-2A	
				EX SN 046-C802	PR SN 046-2015
66400405	CHAIN LINK FENCE, 7'	FOOT	41	41	
66410300	CHAIN LINK FENCE REMOVAL	FOOT	41	41	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	378	378	
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	50	50	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17	17	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	122.4	122.4	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	60	60	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	56	56	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	
X3550600	BITUMINOUS BASE COURSE SUPERPAVE 9"	SQ YD	311	311	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	66	66	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	13	13	
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	24	24	
X5400403	BOX CULVERT END SECTION, SPECIAL, CULVERT NO. 1	EACH	1	1	
XX003008	TRAFFIC CONTROL DETOUR	L SUM	1	1	
Z0003900	BICYCLE RAILING	FOOT	102	102	
Z0005400	BREAKER RUN CRUSHED STONE	TON	779	779	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. DATE      DRAWN BY CHECKED BY

AUGUST 18, 2004 7:00:58PM /SUMQUANT.DGN