

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** (70X, 71X)RS-1, (71X-VBR)DM		CONTRACT NO. 66225		

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
CODE NO.	ITEM	UNIT	TOTAL QTY.	I 000	I000	I000	SFTY-1B	PARKING
				ROADWAY	DETOUR ROADWAY WORK 50% STATE 50% CITY	LINCOLN AVENUE IMPROVEMENTS 100% CITY	SIDEWALK 50% STATE 50% CITY	LANE 50% STATE 50% CITY
				URBAN				Y025
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	1232	1232				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	258	258				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	137	137				
44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	7509		7509			
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	13,891	13,891				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	814	574	240			
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	455	455				
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	7	7				
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	58	58				
50105220	PIPE CULVERT REMOVAL	FOOT	540	540				
50200100	STRUCTURE EXCAVATION	CU YD	674	674				
50300225	CONCRETE STRUCTURES	CU YD	35.5	35.5				
50800105	REINFORCEMENT BARS	POUND	13,220	13,220				
51000305	PIPE HANDRAIL, SPECIAL	FOOT	452	452				
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2				
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2				
54020302	PRECAST CONCRETE BOX CULVERT 3' X 2' (M2T3)	FOOT	84	84				
54020905	PRECAST CONCRETE BOX CULVERT 9' X 5' (M2T3)	FOOT	252	252				
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	84	84				
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	110	110				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	159	159				
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	14	14				
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	69	69				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	7				

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATE	REASON

FILE NAME	BY	DATE

CHECKS		
INT.	DATE	REASON

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

FAU 6108 (IL. RTE. 351)  
SECTION (70X, 71X)RS-1, (71X-VBR)DM  
LASALLE COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE: 01/03/03

DRAWN BY: JETT  
DESIGNED BY: KUNTZMAN  
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.  
OF SPRINGFIELD

COMPUTER FILE NO.  
SUMMARY-03  
PROJECT 01194\_B\_S  
10/30/03-JLJ

REVISIONS	
NAME	DATE