

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** (70X, 71X)RS-1, (71X-VBR)DM CONTRACT NO. 66225				

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE				
				I 000 ROADWAY	I000 DETOUR ROADWAY WORK 50% STATE 50% CITY	I000 LINCOLN AVENUE IMPROVEMENTS 100% CITY	SFTY-18 SIDEWALK 50% STATE 50% CITY	PARKING LANE 50% STATE 50% CITY
				URBAN	80% FED 20% STATE			Y025
60260100	INLETS TO BE ADJUSTED	EACH	1	1				
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60500040	REMOVING MANHOLES	EACH	16	16				
60500060	REMOVING INLETS	EACH	65	63		2		
60600605	CONCRETE CURB, TYPE B	FOOT	130	130				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1026	332		694		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	18,385	18,385				
61101007	STORM SEWERS, PROTECTED, CLASS A, 6"	FOOT	200	200				
61101009	STORM SEWERS, PROTECTED, CLASS A, 8"	FOOT	200	200				
61101011	STORM SEWERS, PROTECTED, CLASS A, 10"	FOOT	200	200				
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5	5				
61139900	STORM SEWERS, SPECIAL 6"	FOOT	200	200				
61140000	STORM SEWERS, SPECIAL 8"	FOOT	200	200				
61140100	STORM SEWERS, SPECIAL 10"	FOOT	200	200				
63200310	GUARDRAIL REMOVAL	FOOT	774	774				
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	14	14				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1				
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	24	24				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3				
67001000	MOBILIZATION	L SUM	1	1				
66901000	BACKFILL PLUGS	CUYD	10	10				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
* 69900105	NON-SPECIAL WASTE DISPOSAL	CUYD	247	247				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				

\* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

FAU 6108 (IL. RTE. 351)  
SECTION (70X, 71X)RS-1, (71X-VBR)DM  
LASALLE COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE: 01/03/03

DESIGNED BY: JETT  
CHECKED BY: COLBROOK

GREEN & BRADFORD, INC.  
CONSULTING ENGINEERS  
10700 W. 111TH ST., SUITE 100, OVERLAND PARK, MO 66211  
(913) 666-1010

COMPUTER FILE NO.  
SUMMARY-06  
PROJECT 01194-B.S  
10/30/03-JLJ

REVISIONS	
NAME	DATE

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATE	REASON

FILE NAME = \$FILE\$	DATE
PLOT SCALE = \$SCALE\$	BY
PLOT DATE = \$DATE\$	
PLOT TIME = \$TIME\$	
OPERATOR = \$OPER\$	
PROFILE	
NOTE BOOK	
NO.	

CHECKS		
INT.	DATE	REASON