DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

F.A.U. RTE. 6108 | SECTION **** | COUNTY LASALLE | TOTAL SHEETS 679 | SHEET NO. 54
STA. ——— TO STA. ———
FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT
*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MAKRING-LINE					THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MAKRING-LINE					TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	WORK ZONE PAVEMENT MARKNG REMOVAL
	4"	6"	8"	12"	24"		4"	6"	8"	12"	24"		
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	SQ. FT.
MAINLINE													
STA. 134+72 TO STA. 139+00	1,067	346	143	142	28	62.4	1,067	346	143	142	28	62.4	882
STA. 139+00 TO STA. 144+00	850	638	173		26	93.6	850	638	173		26	93.6	862
STA. 144+00 TO STA. 149+00	1,661	413	376		42	78.0	1,661	413	376		42	78.0	1,169
STA. 149+00 TO STA. 154+00	1,022	245	158	529	34		1,022	245	158	529	34		1,163
STA. 159+00 TO STA. 164+00	479	619			27		479	619			27		522
STA. 164+00 TO STA. 169+00	638	120					638	120					271
STA. 169+00 TO STA. 174+00	153	444			56		153	444			56		385
STA. 174+00 TO STA. 178+00		192			15			192			15		126
STA. 178+00 TO STA. 182+50		376			30			376			30		248
STA. 182+50 TO STA. 187+00		665			71			665			71		475
STA. 187+00 TO STA. 192+00		363			34			363			34		250
STA. 192+00 TO STA. 197+00		434			52			434			52		321
STA. 197+00 TO STA. 202+00		232			16			232			16		148
STA. 202+00 TO STA. 207+00	1,571	144	20	314	16		1,571	144	20	314	16		950
STA. 207+00 TO STA. 212+00	1,144	155	303	87	43	62.4	1,144	155	303	87	43	62.4	894
STA. 212+00 TO STA. 217+00	1,224	50	14	241	40		1,224	50	14	241	40		760
STA. 217+00 TO STA. 222+00	810	70		183	22		810	70		183	22		530
STA. 222+00 TO STA. 227+00	1,200		223	318	33	46.8	1,200		223	318	33	46.8	977
STA. 227+00 TO STA. 232+00	2,054	60		680			2,054	60		680			1,388
STA. 232+00 TO STA. 237+00	752	120			55		752	120			55		419
STA. 237+00 TO STA. 242+00	877	130			25		877	130			25		405
STA. 242+00 TO STA. 247+00	1,000	120					1,000	120					390
RACCUGLIA ROAD													
STA. 45+60 TO STA. 50+00	283				34		283				34		162
STAGE 2 AT RACCUGLIA ROAD													
STA. 45+60 TO STA. 49+60 (WHITE LINE)							400				18		168
STA. 45+60 TO STA. 49+60 (DOUBLE YELLOW LINE)							800						264
STAGE 3 AT RACCUGLIA ROAD													
STA. 45+60 TO STA. 49+60 (WHITE LINE)							400				37		206
STA. 45+60 TO STA. 49+60 (DOUBLE YELLOW LINE)							800						264
	16,785	5,936	1,410	2,494	699	343.2	19,185	5,936	1,410	2,494	754	343.2	14,599

PAVEMENT REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL	APPROACH REMOVAL SLAB
	SQ. YD.	SQ. YD.
MAINLINE		
STA. 226+01.78 TO STA. 232+66.27	87	213
STA. 178+00 TO STA. 178+90 LT.	47	
RACCUGLIA ROAD		
STA. 45+60 TO STA. 50+00.00	192	
TOTALS	326	213

PERMANENT SURVEY MARKER SCHEDULE

LOCATION	PERMANENT SURVEY MARKERS, TYPE I
	EACH
MAINLINE	
STA. 135+75.00 (P.O.T.)	1
STA. 148+34.86 (P.I.)	1
STA. 167+00.00 (P.O.T.)	1
STA. 183+05.54 (P.I.)	1
STA. 200+21.89 (P.I.)	1
STA. 203+50.00 (P.O.T.)	1
STA. 222+50.00 (P.O.T.)	1
STA. 226+01.78 (INTERSECTION)	1
STA. 229+00.00 (P.O.T.)	1
STA. 245+00.00 (P.O.T.)	1
RACCUGLIA ROAD	
STA. 45+15.35 (P.C.)	1
STA. 47+60.66 (PRC)	1
STA. 48+20.39 (PCC)	1
STA. 49+81.81 (P.T.)	1
TOTALS	14

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
2520 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62703
PROFESSIONAL DESIGN FIRM 184.001470
PHONE (217) 793-3674 FAX (217) 793-3676
REGISTERED ILLINOIS STRUCTURAL ENGINEERING CORPORATION
GBTF793-3674, GBTF793-3676 WILT-WEL - GBSPRINGFIELD@GBTF.COM

COMPUTER FILE NO. SCHEDULE_18
PROJECT 01194_B_S
10/30/03-JLJ

FAU 6108 (IL. RTE. 351) LASALLE COUNTY

F:\LE NAME = J:\01194\DRAWINGS\PART_B\SOUTH PART\SCHEDULE.dgn
PLOT SCALE = 9.99
PLOT DATE = 1/26/2005
PLOT TIME = 2:24:26 PM
OPERATOR = jrego

PROFILE	SURVEYED	BY	DATE
NOTE BOOK	DRAWN		
NO.	CHECKED		
	QUANTITIES		
	STRUCTURE		
	NOTATNS CHKD		