

PLAN SURVEYED BY DATE
 PLOTTED BY DATE
 CHECKED BY DATE
 RT. OF WAY CHECKED
 NO. FILE NAME

PROFILE SURVEYED BY DATE
 PLOTTED BY DATE
 CHECKED BY DATE
 STRUCTURE NOTATION CHECKED
 NO.

LOCATION	BIT. CONCRETE PAVEMENT (FULL-DEPTH) SUPERPAVE 12 3/4" (SQ YD)	BIT. CONCRETE SURFACE COURSE SUPERPAVE MIX "D", N70 (TON)	BIT. CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N70 (TON)	POLYMERIZED BIT. CONCRETE SURFACE COURSE SUPERPAVE MIX "D", N70 (TON)	LEVELING BINDER (MACHINE METH.) SUPERPAVE N70 (TON)	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION (SQ YD)	INCIDENTAL BITUMINOUS SURFACING (TON)	AGGREGATE SURFACE COURSE TYPE B (TON)	AGGREGATE FOR TEMPORARY ACCESS (TON)
ILLINOIS ROUTE 113									
33+00.00 TO 62+00.00				812.1					
62+00.00 TO 73+50.00	452			224.9	226.6				
73+50.00 TO 102+40.00	8627			13.2	86.3				
102+40.00 TO 108+00.00	299			100.5	275.3				
108+00.00 to 110+20.00				49.4					
110+20.00 TO 113+25.00									
SUBTOTAL	9378			1200.1	588.2				
DETOURS									
62+00.00 TO 76+94.50		237.5	305.3			2769			
98+37.01 TO 113+25.00		270.4	347.7			3110			
SUBTOTAL		507.9	653.0			5879			
TOWER ROAD									
3+96.28 TO 7+18.31	118			68.7	89.4				
7+18.31 TO 9+82.00	1663								
SUBTOTAL	1781			68.7	89.4				
MAIN STREET									
310+08.00 TO 310+33.42				22.0	23.8				
INDIAN TRAIL									
10+00.00 TO 10+49.65							131.7		160.2
DRIVEWAYS									
68+57.00 RT							49.6		66.0
84+83.50 RT						3.4	29.2		42.8
100+92.00 RT							49.9		66.5
103+95 RT							50.3		66.9
105+00 LT							54.0		72.0
7+52.00 LT						3.2	55.0		55.1
SUBTOTAL							6.6	288.0	369.3
TOTAL	11159	507.9	653.0	1290.8	701.4	5879	138.3	288.0	529.5

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAU 6194 (ILLINOIS ROUTE 113)
PAVEMENT SCHEDULE
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____