

80% FED.
20% STATE

SUMMARY OF QUANTITIES URBAN		1000-1A		SAFETY 3A HAL LOCATION RIGHT TURN LANE AT LIGHT ROAD	
PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	1000	
20400800	FURNISHED EXCAVATION	CU YD	196	196	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	613		613
25000200	SEEDING, CLASS II	ACRE	1.10	0.97	0.13
25100630	EROSION CONTROL BLANKET	SQ YD	5,314	4,701	613
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	648		648
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	3	3	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,705	4,660	45
40600300	AGGREGATE (PRIME COAT)	TON	125	124	1
40600400	MIXTURE FOR CRACKS, JOINT AND FLANGEWAYS	TON	17	17	
40600895	CONTRSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	335	322	13
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	444	434	10
44000060	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	56,639	56,523	116
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	211		211
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	371		371
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	306		306
44201783	CLASS D PATCH, TYPE IV, 11 INCH	SQ YD	741	741	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	298	298	
60255600	MANHOLES TO BE ADJUSTED	EACH	9	9	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	408		408
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	132		132
* 66900450	SPECIAL WASTE PLANS AND REPORT	LSUM	1		1
* 66900510	BETX - PNAS SOIL ANALYSIS	EACH	2		2
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1		1
* 66900635	LEAD TCLP SOIL ANALYSIS	EACH	2		2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	LSUM	1	1	

80% FED.
20% STATE

SUMMARY OF QUANTITIES URBAN		1000-1A		SAFETY 3A HAL LOCATION RIGHT TURN LANE AT LIGHT ROAD	
PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	1000	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	LSUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	LSUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	10	10	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,705	1,705	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,002	1,002	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	131	131	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	128	128	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,651	2,651	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	296	296	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40,974	40,974	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,755	2,755	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,330	1,330	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,212	1,212	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	128	128	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	781	781	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	781	781	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
88300600	DETECTOR LOOP REPLACEMENT	FOOT	728	728	
X0324890	MTBE SOIL ANALYSIS	EACH	2		2
XX003008	TRAFFIC CONTROL DETOUR	LSUM	1	1	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4,797	4,756	41
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	339		339
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	18	18	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	70	70	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	1,536	1,536	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY MAP
 HORIZ. CHECKED BY RRM
 DATE 11/15/04