

F.A.P. RTE. 591/860	SECTION (12) RS-4	COUNTY KENDALL	TOTAL SHEETS 23	SHEET NO. 7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT # 66432				

CLASS D PATCH, 11 INCH					
LOCATION		SIDE	TYPE II	TYPE III	TYPE IV
FROM	TO	(LT/RT)	SQ YD	SQ YD	SQ YD
644+50	645+00	RT			72.2
645+50	646+00	RT			83.3
646+75	647+75	RT			188.9
744+03	744+43	LT			75.6
752+46	752+86	LT			75.6
756+05	757+35	LT			245.6
TOTAL SQ YD					741.1

MAILBOX TURNOUTS							
LOCATION	WIDTH	LENGTH	AREA	BIT MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	BIT CONC. SURF. CSE. SUPERPAVE. MIX "D", N70	AGGREGATE SHOULDERS
FROM	FT	FT	SQ YD	GALLON	TON	TON	TY. B
645+38	8	67	55.8	4.2	0.1	4.7	15.9
646+46	4	25	11.1	0.8	0.0	0.9	1.7
648+28	4	28	12.4	0.9	0.0	1.0	1.9
649+56	4	30	13.3	1.0	0.0	1.1	2.0
651+18	4	27	12.0	0.9	0.0	1.0	1.8
653+25	4	24	10.7	0.8	0.0	0.9	1.6
654+77	2	16	3.6	0.3	0.0	0.3	0.3
742+12	5	46	25.6	1.9	0.1	2.1	4.9
745+21	7	24	18.7	1.4	0.0	1.6	5.0
747+62	6	40	26.7	2.0	0.1	2.2	6.1
750+49	7	92	71.6	5.4	0.1	6.0	19.0
751+53	6	268	178.7	13.4	0.4	15.0	40.7
754+50	8	18	15.8	1.2	0.0	1.3	4.7
756+18	7	129	100.3	7.5	0.2	8.4	26.7
758+10	3	5	1.7	0.1	0.0	0.1	0.2
758+83	4	39	17.3	1.3	0.0	1.5	2.6
MAILBOX TURNOUT TOTAL				43.1	1.1	48.3	135.0

BITUMINOUS SURFACE REMOVAL			
LOCATION		AVG WIDTH	BIT SURF REM
FROM	TO	FEET	SQ YD
618+87	659+48	28.4	12,818.2
659+89	681+38	43.6	10,400.7
700+37	776+19	33.4	28,132.3
TOTAL			51,351.2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 11/15/04

DRAWN BY MAP
CHECKED BY RRM