

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(38-5)T-2	IROQUOIS	11	2
STA. 763+73		TO STA. 778+73		
FED. ROAD DIST. NO. ILLINOIS NON-FED. AID PROJECT				

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The Contractor shall verify all dimensions and elevations prior to beginning construction operations.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

The cost of any saw cuts made to complete the work as described in plan details, unless otherwise noted shall not be paid for separately but shall be included in the various pay items involved.

The finished earthwork shall have a vegetation sustaining soil covering the top four inches (4") in areas to be seeded or sodded. The vegetation sustaining soil required shall be measured and paid for in accordance with Section 204 of the Standard Specifications.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.

All areas disturbed by the Contractors operations and new earthwork shall be graded, fertilized and seeded according to the applicable portions of Section 250 of the Standard Specifications and as directed by the Engineer. This work shall not be paid for separately but shall be included with the related earthwork items.

Seeding shall not be permitted at any time when the ground is frozen, wet, or in an untillable condition. Locations to be seeded will be determined by the Engineer.

Abandoned underground utilities that conflict with construction shall be disposed of outside the limits of the right of way according to Article 202.03 of the Standard Specifications and as directed by the Engineer. This work will not be paid for separately but shall be included in the cost of earth excavation.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

Reinforcement bars shall conform to the requirements of AASHTO M 31 or M322 Grade 60.

DATE: 12-21-04

PREPARED BY: *Bruce C. Muehlen*
DISTRICT OPERATIONS ENGINEER

EXAMINED BY: *Robert J. [Signature]*
DISTRICT CONSTRUCTION ENGINEER

T. P. Sanchez-Lopez
DISTRICT STUDIES & PLANS ENGINEER
Kenneth R. [Signature]
DISTRICT MATERIALS ENGINEER

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. 1"=20' HORIZ. 1"=40' DATE 10/21/04 DRAWN BY RW CHECKED BY

FILE NAME: CHANGES/CH14/DETAILS.DGN