

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	153-301	LIVINGSTON	14	3
STA. 331+64		TO STA. 338+18		
FED. ROAD DIST. NO.		ILLINOIS		

SUMMARY OF QUANTITIES

1000

CONSTRUCTION CODE:

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	1843
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1814
31200100	STABILIZED SUB-BASE 4"	SQ YD	1814
42100300	CONTINUOUSLY REINFORCED ^{PORTLAND CEMENT} CONCRETE PAVEMENT 10"	SQ YD	1814
42100900	PAVEMENT REINFORCEMENT 10"	SQ YD	1814
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	640
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	1814
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	569
48101200	AGGREGATE SHOULDERS TYPE B	TON	84
48300500	PORTLAND CEMENT CONCRETE SHOULDER 10"	SQ YD	1209
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2
60107600	PIPE UNDERDRAINS 4"	FOOT	732
60107800	PIPE UNDERDRAINS 8"	FOOT	588
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	34
60108300	PIPE UNDERDRAINS 8" (SPECIAL)	FOOT	34
60615400	PAVED DITCH TYPE A-15	FOOT	105
64200105	SHOULDER RUMBLE STRIPS	FOOT	1360
67100100	MOBILIZATION	L SUM	1

PLT DATE = SEPTEMBER 21, 2004
FILE NAME = c:\msh\con324\detm1.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 09/21/04

DRAWN BY RW
CHECKED BY