

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(53-3)1	LIVINGSTON	14	7
STA. 331+64		TO STA. 338+18		
FED. ROAD DIST. NO. ILLINOIS				

DRAINAGE SCHEDULE

LOCATION	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAIN 4"	PIPE UNDERDRAIN 8"	PIPE UNDERDRAIN 4" (SPECIAL)	PIPE UNDERDRAIN 8" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	PAVED DITCH TYPE A-15
	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	FOOT
STAGE I								
331+54 TO 333+19	1	165	165					
333+19		17						
333+19 TO 333+44		25	25					
333+44 TO 333+50		6	6					
333+50					17	17	1	
333+50 TO 334+49		99		99				
334+49 TO 335+19		70		70				
335+19 TO 336+44		125		125				
336+44 TO 337+60		116	116					
337+60	1	17						
337+60 TO 338+14		54	54					
SUBTOTAL	2	694	366	294	17	17	1	0
STAGE II								
331+54 TO 333+19	1	165	165					
333+19		17						
333+19 TO 333+44		25	25					6
333+44 TO 333+50		12	6					
333+50					17	17	1	99
333+50 TO 334+49		198		99				
334+49 TO 335+19		70		70				
335+19 TO 336+44		125		125				
336+44 TO 337+60		116	116					
337+60	1	17						
337+60 TO 338+14		54	54					
SUBTOTAL	2	799	366	294	17	17	1	105
TOTALS	4	1493	732	588	34	34	2	105

PLOT DATE: SEPTEMBER 21, 2004
 FILE NAME: c:\man\05\cns24\chan11.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
 HORIZ. _____
 DATE 09/21/04

DRAWN BY RW
 CHECKED BY _____