

SUMMARY OF QUANTITIES

F.A.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-57-	*	**	.76.	..7.

CONTRACT NO. 70028
 *15,18-20)RS-2&(15-22)RS-2
 **COLES & CUMBERLAND

LOCATION OF WORK: CUMBERLAND

COLES

FM STA. 286+88.78 TO STA. 340+00.00 &
 FM STA. 482+00.00 TO STA. 691+79.69 &
 FM STA. 119+16.79 TO STA. 286+88.78
 FM STA. 815+87.69 TO STA. 841+07.00
 FM STA. 691+79.69 TO STA. 815+87.69

RURAL

I-57 BRIDGE
 S. N. 015-0003
 S. N. 015-0004
 4 LANE
 90% FED
 10% STATE
 SAFETY-2A

I-57 BRIDGE
 S. N. 015-0032
 URBAN
 4 LANE
 90% FED
 10% STATE
 SAFETY-2A

CODE NO.	PAY ITEM	UNIT	QUANTITY	CONSTRUCTION TYPE CODE:	10% STATE 1000	90% FED 1000	10% STATE 1000	90% FED 1000	10% STATE 1000	90% FED 1000
78200455	BIDIRECTIONAL GUARDRAIL REFLECTOR	EACH	30.0							30.0
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	40.0		10.0		13.0		14.0	3.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2,256.0		897.0		952.0		407.0	
X0322729	MATERIAL TRANSFER DEVICE	TON	58,078.0		19,737.0		27,242.0		11,099.0	
X0310000	CONCRETE REPAIR FOR PIPE UNDERDRAIN REMOVAL	EACH	100.0							100.0
X3550500	BITUMINOUS BASE COURSE, SUPERPAVE, 8"	SQ. YD.	1,391.0				1,391.0			
X4032500	BITUMINOUS MATERIALS (COVER & SEAL COATS), SPECIAL	GALLON	1,688.0				1,295.0		393.0	
X4040100	SEAL COAT AGGREGATE, SPECIAL	TON	84.0				64.4		19.6	
X4066530	POLYMER BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'D', N105	TON	30,430.0		7,951.0		15,660.0		6,819.0	
X4066660	POLYMER BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL19.0, N105	TON	27,648.0		11,786.0		11,582.0		4,280.0	
X4066920	POLYMER LEVELING BINDER, (MACHINE METHOD) SUPERPAVE, N105	TON	682.0		155.0		527.0			
X4409420	BITUMINOUS SURFACE REMOVAL, 3 1/4"	SQ. YD.	68,133.0				44,602.1		23,530.9	
X4420051	CLASS A PATCH, TYPE II, 11 1/4 INCH	SQ. YD.	57.0				572.0			
X4420052	CLASS A PATCH, TYPE III, 11 1/4 INCH	SQ. YD.	16.0				16.0			
X0310000	CONCRETE REPAIR FOR PIPE UNDERDRAIN REMOVAL (SPECIAL)	EACH	2,250.0							2,250.0
X6610100	BITUMINOUS CURB REPAIR	FOOT	130.0				55.5		74.5	
X7015005	CHANGEABLE MESSAGE SIGN	CAL. DAY	56.0		28.0		28.0			
XX005496	TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)	EACH	3.0		3.0					
Z0017100	DOWEL BARS	EACH	140.0		140.0					
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4.0		4.0					
Z0030150	IMPACT ATTENUATOR, NON-REDIRECTIVE, TEST LEVEL 3	EACH	8.0		4.0		2.0		2.0	
Z0075300	TIE BARS	EACH	65.0						65.0	
Z0076600	TRAINEES	HOUR	1,000		500		500			

* SPECIALTY ITEMS

** SFTY-3N

Y080

REVISOR 1-10-05

REVISOR 2-22-05