

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57			76	6

CONTRACT NO. 70028
 *15,18-201RS-2&15-221RS-2
 **COLES & CUMBERLAND

LOCATION OF WORK: CUMBERLAND

COLES

FM STA. 286+88.78 TO STA. 340+00.00 & FM STA. 482+00.00 TO STA. 691+79.69 & FM STA. 815+87.69 TO STA. 841+07.00	FM STA. 119+16.79 TO STA. 286+88.78	FM STA. 691+79.69 TO STA. 815+87.69	RURAL I-57 BRIDGE S. N. 015-0003 S. N. 015-0004 4 LANE 90% FED 10% STATE SAFETY-2A
--	--	--	--

CODE NO.	PAY ITEM	UNIT	QUANTITY	CONSTRUCTION TYPE CODE:	10% STATE 1000	90% FED 1000	10% STATE 1000	90% FED 1000	10% STATE 1000	90% FED 1000
50300225	CONCRETE STRUCTURES	CU. YD.	1.5							1.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	230.0							230.0
50901001	STEEL BRIDGE RAIL	FOOT	469.0							469.0
51500200	RELOCATING NAME PLATES	EACH	4.0			4.0				
6010060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	291.0				202.0		89.0	
60107600	PIPE UNDERDRAINS, 4"	FOOT	134,447.0				111,424.8		23,022.2	
60108100	PIPE UNDERDRAINS, 4" SPECIAL	FOOT	6,150.0				4,280.0		1,870.0	
60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	21.0				11.0		10.0	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	3,815.5		775.0		1,353.0		1,662.5	25.0
* 63000130	STEEL PLATE BEAM GUARDRAIL, TYPE A, SPECIAL	FOOT	25.0							25.0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7.0				2.0		4.0	1.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	10.0				4.0		6.0	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	6.0		2.0					4.0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)	EACH	40.0		10.0		14.0		13.0	3.0
* 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6, SPECIAL	EACH	24.0		4.0		8.0		12.0	
* 63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B, SPECIAL	EACH	10.0		4.0		4.0		2.0	
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	5,300.0		1,387.5		2,023.9		1,563.6	325.0
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	2,050.0		412.5		200.0		125.0	1,312.5
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2.0		2.0					
63400105	GUARD POSTS	EACH	42.0		4.0		28.0		10.0	
64200105	SHOULDER RUMBLE STRIP	FOOT	215,236.0		64,769.0		108,039.0		42,428.0	
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL. MO.	12.0		6.0		4.0		2.0	
67100100	MOBILIZATION	L. SUM	1.0		0.5		0.3		0.2	
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L. SUM	1.0		0.5		0.3		0.2	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	14.0		2.0		8.0		4.0	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1.0				0.7		0.3	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L. SUM	1.0		0.5		0.3		0.2	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L. SUM	1.0		0.5		0.3		0.2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DAY	39.0		10.0		20.0		9.0	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	38,353.0		10,954.0		19,445.0		7,954.0	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	250,851.0		71,697.0		126,333.0		52,821.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	85,386.0		24,377.0		43,033.0		17,976.0	
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	28,355.0		8,326.0		14,175.0		5,854.0	
* 78008310	POLYUREA PAVEMENT MARKING TYPE II-LINE 4"	FOOT	243,011.0		70,615.0		147,580.0		24,816.0	
* 78008330	POLYUREA PAVEMENT MARKING TYPE II-LINE 6"	FOOT	165.0				165.0			
* 78008340	POLYUREA PAVEMENT MARKING TYPE II-LINE 8"	FOOT	9,287.0		1,738.0		3,099.3		4,449.7	
* 78008350	POLYUREA PAVEMENT MARKING TYPE II-LINE 12"	FOOT	80.0				80.0			
* 78008370	POLYUREA PAVEMENT MARKING TYPE II-LINE 24"	FOOT	105.0		40.0		65.0			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,124.0		897.0		1,527.0		700.0	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	52.0				16.0		36.0	
* 78200450	MONODIRECTIONAL GUARDRAIL REFLECTOR	EACH	156.0		45.0		55.0		56.0	

* SPECIALTY ITEMS