

SUMMARY OF QUANTITIES

RURAL  
 STA. 64+00  
 TO  
 STA. 74+00  
 80% FEDERAL  
 20% STATE

CONSTRUCTION TYPE CODE

X080-2A

CODE NO.	PAY ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	42.0
20700220	POROUS GRANULAR EMBANKMENT	CUYD	81.0
25000200	SEEDING CLASS 2	ACRE	1.0
25000400	NITROGEN FERTILIZER	POUND	90.0
25000500	PHOSPHORUS FERTILIZER	POUND	90.0
25000600	POTASSIUM FERTILIZER	POUND	90.0
25100105	MULCH METHOD 1	ACRE	1.0
28000900	FENCE EROSION CONTROL	FOOT	400.0
28100107	STONE RIPRAP, CLASS A-4	SQYD	664.0
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQYD	664.0
40600100	BITUMINOUS MATERIALS PRIME COAT	GAL	214.0
40600980	BITUMINOUS SURFACE REMOVAL, BUTT JOINT	SQYD	160.0
40800010	BITUMINOUS MATERIALS PRIME COAT	GALLON	25.0
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	35.0
42001165	BRIDGE APPROACH PAVEMENT	SQYD	174.0
42001300	PROTECTIVE COAT	SQYD	442.0
42001430	BRIDGE APPROACH PAVEMENT CONNNECTOR (FLEXIBLE)	SQYD	32.0
44000025	BITUMINOUS SURFACE REMOVAL, SPECIAL	SQYD	270.0
44000100	PAVEMENT REMOVAL	SQYD	240.0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1.0
50104000	BRIDGE RAIL REMOVAL	EACH	253.0
50200100	STRUCTURE EXCAVATION	CUYD	81.7
50300225	CONCRETE STRUCTURES	CUYD	1.0
50300260	BRIDGE DECK GROOVING	SQYD	576.0
50301200	CONCRETE WEARING SURFACE	SQYD	418.0
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQFT	3,975.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,330.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5,450.0
*50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	265.0
51500100	NAME PLATES	EACH	1.0
55022000	STORM SEWER CLASS 2 REINFORCED CONCRETE PIPE CLASS 3, 24"	FOOT	20.0
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4.0
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL, TANGENT	EACH	4.0
*63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	98.0
67000400	ENGINEERS FIELD OFFICE TYPE A	CAL MO	6.0
67100100	MOBILIZATION	L SUM	1.0
*78001110	PAINT PAVEMENT MARKING, LINE 4"	FOOT	2,300.0
*78201000	TERMINAL MARKER, DIRECT APPLIED,	EACH	4.0
X0322379	CONCRETE SEALER	SQYD	52.1
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50	TON	179.0
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	278.0
X7013015	TRAFFIC CONTROL AND PROTECTION, FOR ROAD CLOSURE	L SUM	1.0
XX005369	TRAFFIC CONTROL AND PROTECTION, TEMPORARY DETOUR	L SUM	1.0

\*SPECIALTY ITEMS