

SUMMARY OF QUANTITIES

• MACON, MOULTRIE & PIATT
CONTRACT NO. 70394

CODE NO	ITEM	UNIT	LOCATION OF WORK:				
			FAP 323 125+45.00 TO 62+38.20	FAP 323 125+45.00 TO 291+53.00 (URBAN)	FAP 323 291+53.00 TO 513+86.02 (RURAL)	FAP 323 0+00.00 TO 62+38.20 (RURAL)	FAP 323 0+00.00 TO 62+38.20 (RURAL)
		CONSTRUCTION TYPE CODE:	100% STATE I000 TOTAL QUANTITY	100% STATE I000 MACON CO. QUANTITY	100% STATE I000 MACON CO. QUANTITY	100% STATE I000 MOULTRIE CO. QUANTITY	100% STATE I000 PIATT CO. QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	29.0	29.0			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14,844.0	5,969.0	6,866.0	2,009.0	
40600300	AGGREGATE (PRIME COAT)	TON	298.0	119.4	137.6	41.0	
40600895	CONSTRUCT TEST STRIP	EACH	1.0	1.0			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	862.0	588.3	193.7	80.0	
40600990	TEMPORARY RAMP	SQ YD	135.0	82.8	32.2	20.0	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	537.0	245.5	246.5	34.0	11.0
40800030	AGGREGATE (PRIME COAT)	TON	11.0	4.8	5.0	1.0	0.2
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	451.0	206.2	206.8	29.0	9.0
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ YD	5,359.0	2,455.0	2,461.0	337.0	106.0
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	144,065.0	53,638.4	70,325.7	20,100.9	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,479.0	865.7	1,247.3	366.0	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	815.0	815.0			
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	169.0	169.0			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3.0	2.0		1.0	
67100100	MOBILIZATION	L SUM	1.0	1.0			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,229.0	4,228.1	5,499.9	2,501.0	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47.0	47.0			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	103,379.0	38,955.0	49,902.0	14,522.0	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,831.0	704.0	710.0	417.0	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47.0	47.0			
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	296.0	236.0		60.0	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	103,379.0	38,955.0	49,902.0	14,522.0	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	570.0	227.0	265.0	78.0	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	570.0	227.0	265.0	78.0	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	7,443.0		5,754.0	1,689.0	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4,214.0	4,214.0			
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	458.0	164.0	192.7	101.3	
• XZ193400	SURVEY MARKER, TYPE 2 (SPECIAL)	EACH	5.0	4.0	1.0		
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	279.0	101.8	116.4	60.8	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0			

• Specialty Item