

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(139,140)RS-3	•	19	12

• MACON, MOULTRIE & PIATT
CONTRACT NO. 70394

SCHEDULE OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS - 78000100

RIGHT TURN ARROW (LARGE SIZE)

STATION	QUANTITY (SQ. FT.)
289+03.00	15.6
289+64.00	15.6
290+25.00	15.6
TOTAL = 46.80	
FINAL TOTAL = 47.00	

THERMOPLASTIC PAVEMENT MARKING - LINE 4" - 78000100

WHITE LINE - 4"

STATION	TO	STATION	LENGTH (FT)
LT. & RT. 288+50		LT. & RT. 290+86	236.00
RT. 62+08.20		RT. 62+38.20	30.00
LT. 62+08.20		LT. 62+38.20	30.00
TOTAL =			296.00
FINAL TOTAL =			296.00

PAINT PAVEMENT MARKING - LINE 4" - 78000200

WHITE LINE MACON TOTAL	=	75,421.60
YELLOW LINE 4" MACON TOTAL	=	13,434.78
WHITE LINE MOULTRIE TOTAL	=	12,356.40
YELLOW LINE MOULTRIE TOTAL	=	2,165.37
TOTAL =		103,378.15
FINAL TOTAL =		103,379.00

BITUMINOUS SHOULDERS SUPERPAVE 6" - 48202400

STATION	TO	STATION	LENGTH (FT.)	WIDTH (FT.)	QUANTITY (SQ. YD.)
285+79.20		290+86.00	506.80	3.00	168.93
TOTAL =					168.93
FINAL TOTAL =					169.00

SURVEY MARKER TYPE 2 (SPECIAL) - XZ193400

STATION	QUANTITY (EACH)	
199+58.23 (BK), 199+67.1 (AH)	1	
216+06.15	1	
225+03.7 (BK), 224+82.78 (AH)	1	
249+72.35	1	
294+00.22	1	
TOTAL =		5
FINAL TOTAL =		5