

steffenmk
10/26/2004
c:\projects\74048d\402904pa.dgn

SOQ

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	•	JEFFERSON	11	3

FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT NO.
CONTRACT NO. 74048
• (13-2)RS-2,13ZRS-3

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	QUANTITIES	I 000-2A		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4865	4865		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	48652	48652		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10	10		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5185	5185		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1730	1730		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	982.8	982.8		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18650	18650		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3250	3250		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	620	620		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	490	490		
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3260	3260		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	530	530		
78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	170	170		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1960	1960		
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	4768	4768		

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. _____
 HORIZ. _____
DATE _____ DRAWN BY _____
 CHECKED BY _____