

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
877	•	WHITE	6	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• D-7 BIT. RESURF. 2005-5

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS SURFACE REMOVAL, VAR. DEPTH	BITUMINOUS SURFACE REMOVAL, BUTT JOINT	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N70
				SQ YD	SQ YD	GALLON	TON	TON
STA 445+89 TO STA 446+19	30.00	30	90		100	9		7
STA 446+19 TO STA 459+82	1363.00	26	3938	3940		371	8	336
STA 459+82 TO STA 0+30	30.00	28	100		90	10		7
<b>TOTALS</b>			4128	3940	190	390	8	350

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**PAVING SCHEDULE**

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY

PLOT DATE = 12/21/2004  
FILE NAME = #FILE#  
PLOT SCALE = #SCALE#  
REFERENCE = #REF#